

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: <b>ML-22792</b>	8. SURFACE: <b>State</b>
1A. TYPE OF WORK: <b>DRILL</b> <input checked="" type="checkbox"/> <b>REENTER</b> <input type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: <b>OIL</b> <input type="checkbox"/> <b>GAS</b> <input checked="" type="checkbox"/> <b>OTHER</b> _____ <b>SINGLE ZONE</b> <input type="checkbox"/> <b>MULTIPLE ZONE</b> <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: <b>UNIT #891008900A</b>	
2. NAME OF OPERATOR: <b>KERR MCGEE OIL &amp; GAS ONSHORE L.P.</b>				9. WELL NAME and NUMBER: <b>NBU 1021-19E</b>	
3. ADDRESS OF OPERATOR: <b>1368 S 1200 E</b> CITY <b>VERNAL</b> STATE <b>UT</b> ZIP <b>84078</b>			PHONE NUMBER: <b>(435) 781-7024</b>	10. FIELD AND POOL, OR WILDCAT: <b>NATURAL BUTTES</b>	
4. LOCATION OF WELL (FOOTAGES)  AT SURFACE: <b>2146'FNL, 879'FWL LOT 2</b>  AT PROPOSED PRODUCING ZONE:				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:  <b>SWNW 19 10S 21E</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE:  <b>15.7 MILES SOUTH OF OURAY, UTAH</b>				12. COUNTY: <b>UINTAH</b>	13. STATE: <b>UTAH</b>
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET)  <b>879'</b>		16. NUMBER OF ACRES IN LEASE:  <b>643.5</b>		17. NUMBER OF ACRES ASSIGNED TO THIS WELL:  <b>40.00</b>	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>REFER TO TOPO C</b>		19. PROPOSED DEPTH:  <b>9,620</b>		20. BOND DESCRIPTION:  <b>RLB0005237</b>	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.):  <b>5192'GL</b>		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION:	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
<b>12 1/4"</b>	<b>9 5/8</b>	<b>H-40</b>	<b>32.3#</b>	<b>2,000</b>	<b>265 SX CLASS G</b>	<b>1.18 YIELD</b>	<b>15.6 PPG</b>
<b>7 7/8"</b>	<b>4 1/2</b>	<b>I-80</b>	<b>11.6#</b>	<b>9,620</b>	<b>2030 SX 50/50 POZ</b>	<b>1.31 YIELD</b>	<b>14.3 PPG</b>

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER  <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN  <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) <u><b>SHEILA UPCHEGO</b></u>	TITLE <u><b>SENIOR LAND ADMIN SPECIALIST</b></u>
SIGNATURE <u><i>[Signature]</i></u>	DATE <u><b>1/23/2007</b></u>

(This space for State use only)

API NUMBER ASSIGNED: **43-047-39606**

**Approved by the  
Utah Division of  
Oil, Gas and Mining**  
APPROVAL:

**RECEIVED  
FEB 02 2007**

(11/2001)

Date: **02-28-07**  
By: *[Signature]* DIV. OF OIL, GAS & MINING

1928 Brass Cap,  
0.6' High, Pile of  
Stones, Set Marked  
Stone


T10S, R21E, S.L.B.&M.

Kerr McGee Oil & Gas Onshore LP

Well location, NBU #1021-19E, located as  
shown in the SW 1/4 NW 1/4 of Section 19,  
T10S, R21E, S.L.B.&M. Uintah County, Utah.

### BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE  
NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN  
FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH,  
UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC  
MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT  
OF THE INTERIOR, GEOLOGICAL SURVEY. SAID  
ELEVATION IS MARKED AS BEING 5238 FEET.




### CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE WAS PREPARED FROM  
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER  
SUPERVISION AND THAT THE SAME ARE TRUE TO THE  
BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 101319  
STATE OF UTAH

UNTAH ENGINEERING & LAND SURVEYING  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 10-29-06	DATE DRAWN: 11-08-06
PARTY G.O. B.H. S.L.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE Kerr McGee Oil & Gas Onshore LP	



### BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

(NAD 83)  
LATITUDE = 39°56'04.44" (39.934567)  
LONGITUDE = 109°36'03.96" (109.601100)  
(NAD 27)  
LATITUDE = 39°56'04.57" (39.934603)  
LONGITUDE = 109°36'01.48" (109.600411)

### LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

R R  
20 21  
E E

NBU 1021-19E  
SW/NW, LOT 2, SEC. 19, T10S, R21E  
UINTAH COUNTY, UTAH  
ML-22792

ONSHORE ORDER NO. 1

***DRILLING PROGRAM***

1. **Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	1156'
Top of Birds Nest Water	1392'
Mahogany	1954'
Wasatch	4415'
Mesaverde	7431'
MVU2	8425'
MVL1	8976'
TD	9620'

2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Water	Green River	1156'
	Top of Birds Nest Water	1392'
	Mahogany	1954'
Gas	Wasatch	4415'
Gas	Mesaverde	7431'
Gas	MVU2	8425'
Gas	MVL1	8976'
Water	N/A	
Other Minerals	N/A	

3. **Pressure Control Equipment** (Schematic Attached)

*Please refer to the attached Drilling Program.*

4. **Proposed Casing & Cementing Program:**

*Please refer to the attached Drilling Program.*

5. **Drilling Fluids Program:**

*Please refer to the attached Drilling Program.*

6. **Evaluation Program:**

*Please refer to the attached Drilling Program.*

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 9620' TD, approximately equals 5964 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 3848 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

*Drilling is planned to commence immediately upon approval of this application.*

9. **Variances:**

*Please refer to the attached Drilling Program.*

10. **Other Information:**

*Please refer to the attached Drilling Program.*

**KERR-McGEE OIL & GAS ONSHORE LP**  
**DRILLING PROGRAM**

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP	DATE	January 23, 2007	
WELL NAME	NBU 1021-19E	TD	9,620'	MD/TVD
FIELD	Natural Buttes	COUNTY	Uintah	STATE Utah
SURFACE LOCATION	SW/NW LOT 2, SEC. 19, R10S, R21E 2146'FNL, 879'FWL			BHL Straight Hole
	Latitude: 39.934567	Longitude: 109.601100		
OBJECTIVE ZONE(S)	Wasatch/Mesaverde			
ADDITIONAL INFO	Regulatory Agencies: UDOGM (SURF & MINERALS), BLM, Tri-County Health Dept.			

GEOLOGICAL FORMATION		MECHANICAL			
LOGS	TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
40'			14"		
			12-1/4"	9-5/8", 32.3#, H-40, STC	Air mist
Catch water sample, if possible, from 0 to 4,415'					
Green River @ 1,156'					
Top of Birds Nest Water @ 1392'					
Mahogany @ 1,954'					
Preset f/ GL @					
2,000' MD					
Note: 12.25" surface hole will usually be drilled ±400' below the bottom of lost circulation zone. Drilled depth may be ±200' of the estimated set depth depending on the acutal depth of the loss zone.					
Mud logging program TBD					
Open hole logging program f/ TD - surf csg					
Wasatch @ 4,415'			7-7/8"	4-1/2", 11.6#, 1-80 or equivalent LTC casing	Water/Fresh Water Mud 8.3-11.5 ppg
Mverde @ 7,431'					
MVU2 @ 8,425'					
MVL1 @ 8,976'					
TD @ 9,620'					Max anticipated Mud required 11.5 ppg



# **KERR-McGEE OIL & GAS ONSHORE LP** **DRILLING PROGRAM**

## **CASING PROGRAM**

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				2270	1370	254000
SURFACE	9-5/8"	0 to 2000	32.30	H-40	STC	0.62*****	1.46	4.49
						7780	6350	201000
PRODUCTION	4-1/2"	0 to 9620	11.60	I-80	LTC	2.14	1.10	2.06

- 1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point)  
2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft-partial evac gradient x TD)  
(Burst Assumptions: TD = 11.5 ppg) .22 psi/ft = gradient for partially evac wellbore  
(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoyn.Fact. of water)  
MASP 3636 psi

\*\*\*\*\* Burst SF is low but csg is much stronger than formation at 2000'. EMW @ 2000' for 2270# is 21.8 ppg or 1.13 psi/ft

## **CEMENT PROGRAM**

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	50		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE Option 2			<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>				
	LEAD	1500	Prem cmt + 16% Gel + 10 pps gilsonite +.25 pps Flocele + 3% salt BWOC	170	35%	11.00	3.82
	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,910'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	430	60%	11.00	3.38
	TAIL	5,710'	50/50 Poz/G + 10% salt + 2% gel +.1% R-3	1600	60%	14.30	1.31

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

## **FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

## **ADDITIONAL INFORMATION**

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney

DATE: \_\_\_\_\_



DRILLING SUPERINTENDENT:

Randy Bayne

DATE: \_\_\_\_\_

NBU1021-19E DHD.xls

# 5M BOP STACK and CHOKE MANIFOLD SYSTEM



NBU 1021-19E  
SW/NW LOT 2, SEC. 19, T10S, R21E  
Uintah County, UT  
ML-22792

**ONSHORE ORDER NO. 1**

***MULTI-POINT SURFACE USE & OPERATIONS PLAN***

**1. Existing Roads:**

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

**2. Planned Access Roads:**

Approximately 0.2 +/- miles of new access road is proposed. Refer to Topo Map B for the location of the proposed access road.

Approximately 0.2 +/- miles of re-habed road needs upgraded. Refer to Topo Map B.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet. Appropriate water control will be installed to control erosion.

***Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site.***

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

**3. Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

**4. Location of Existing & Proposed Facilities:**

*The following guidelines will apply if the well is productive.*

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.



A dike will be constructed completely around those production facilities which contain

fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Carlsbad Canyon, standard color number 2.5Y 6/2.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Approximately 3450' +/- of 4" pipeline is proposed from the proposed pipeline for the 1021-19C to the proposed location Refer to Topo Map D.

Approximately 1415' +/- of 4" pipeline is proposed from an existing pipeline to the proposed location. Please refer to Topo Map D.

**5. Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

**6. Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

**7. Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner and felt will be used, it will be a minimum of 20 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E.

**8. Ancillary Facilities:**

None are anticipated.

**9. Well Site Layout: (See Location Layout Diagram)**

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

The reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be

three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Location size may change prior to the drilling of the well due to current rig availability. If the proposed location is not large enough to accommodate the drilling rig the location will be re-surveyed and a Form 9 shall be submitted.

**10. Plans for Reclamation of the Surface:**

*Producing Location:*

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

A plastic, nylon reinforced liner will be used; it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

*Dry Hole/Abandoned Location:*

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

**11. Surface Ownership:**

SITLA  
675 East 500 South, Suite 500  
Salt Lake City, UT 84102

**12. Other Information:**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey will be submitted when report becomes available.

This location is not within 460' from the boundary of the Natural Buttes Unit, nor is it within 460' of any non-committed tract lying within the boundaries of the Unit.

**13. Lessee's or Operators's Representative & Certification:**

Sheila Upchego  
Senior Land Admin Specialist  
Kerr-McGee Oil & Gas Onshore LP  
1368 South 1200 East.  
Vernal, UT 84078  
(435) 781-7024

Randy Bayne  
Drilling Manager  
Kerr-McGee Oil & Gas Onshore LP  
1368 South 1200 East  
Vernal, UT 84078  
(435)781-7018


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by State Surety Bond #RLB0005237.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

  
Sheila Upchego

1/23/2007

Date

# Kerr-McGee Oil & Gas Onshore LP

NBU #1021-19E

SECTION 19 T10S, R21E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 11.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 2.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE JUNCTION OF THIS ROAD AND A REHABED ROAD TO THE WEST; TURN RIGHT AND PROCEED IN A WESTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 46.7 MILES.

# Kerr-McGee Oil & Gas Onshore LP

**NBU #1021-19E**

LOCATED IN UTAH COUNTY, UTAH  
SECTION 19, T10S, R21E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: WESTERLY



- Since 1964 -

**UELS**

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

**LOCATION PHOTOS**

**11 03 06**  
MONTH DAY YEAR


**PHOTO**

TAKEN BY: G.O.

DRAWN BY: C.P.

REVISED: 00-00-00





# LEGEND:

○ PROPOSED LOCATION

Kerr-McGee Oil & Gas Onshore LP

NBU #1021-19E

SECTION 19, T10S, R21E, S.L.B.&M.

2146' FNL 879' FWL



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



**TOPOGRAPHIC**  
**MAP**

**11 03 06**  
 MONTH DAY YEAR


SCALE: 1:100,000 DRAWN BY: C.P. REVISED: 00-00-00











**PROPOSED LOCATION:  
NBU #1021-19E**

# **LEGEND:**

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

**Kerr-McGee Oil & Gas Onshore LP**

**NBU #1021-19E  
SECTION 19, T10S, R21E, S.L.B.&M.  
2146' FNL 879' FWL**



**Utah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813




**TOPOGRAPHIC  
MAP**

**11 03 06**  
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00







APPROXIMATE TOTAL PIPELINE DISTANCE = 3,450' +/-

APPROXIMATE TOTAL PIPELINE DISTANCE = 1,415' +/-

# LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE
- PROPOSED PIPELINE (SERVICING OTHER WELLS)



Kerr-McGee Oil & Gas Onshore LP

NBU #1021-19E  
SECTION 19, T10S, R21E, S.L.B.&M.  
2146' FNL 879' FWL



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

TOPOGRAPHIC  
MAP

11 03 06  
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00





# Kerr-McGee Oil & Gas Onshore LP

NBU #1021-19E

PIPELINE ALIGNMENT

LOCATED IN UINTAH COUNTY, UTAH

SECTION 19, T10S, R21E, S.L.B.&M.



PHOTO: VIEW FROM TIE-IN POINT

CAMERA ANGLE: WESTERLY



PHOTO: VIEW OF PIPELINE ALIGNMENT

CAMERA ANGLE: WESTERLY



UELS

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

PIPELINE PHOTOS

11 03 06  
MONTH DAY YEAR

PHOTO

TAKEN BY: G.O.

DRAWN BY: C.P.

REVISED: 00-00-00

# Kerr-McGee Oil & Gas Onshore LP

FIGURE #1


## LOCATION LAYOUT FOR

NBU #1021-19E

SECTION 19, T10S, R21E, S.L.B.&M.

2146' FNL 879' FWL

Proposed Access Road




SCALE: 1" = 50'  
DATE: 11-08-06  
Drawn By: S.L.

Approx.  
Top of  
Cut Slope

Pit  
Topsoil

### NOTE:

Flare Pit is to be located  
a min. of 100' from the  
Well Head. Reserve Pit Backfill  
& Spoils Stockpile



FLARE PIT C-5.8'  
El. 197.1'

El. 205.2'  
C-23.9'  
(btm. pit)

El. 203.0'  
C-21.7'  
(btm. pit)

RESERVE PITS  
(10' Deep)  
Total Pit Capacity  
W/2 of Freeboard  
= 9,850 Bbls. ±  
Total Pit Volume  
= 2,780 Cu. Yds.

Reserve Pit Backfill  
& Spoils Stockpile

PIPE TUBS

PIPE RACKS

C-1.1'  
El. 192.4'

C-5.8'  
El. 197.1'

LIGHT PLANT

BOILER

PUMP HOUSE

TRASH

PROPANE STORAGE

C-0.6'  
El. 191.9'

C-5.0'  
El. 196.3'

C-5.2'  
El. 196.5'

Topsoil Stockpile

F-7.0'  
El. 184.3'

Sta. 3+50

Approx.  
Toe of  
Fill Slope

Round Corners  
as Needed

Existing  
Drainage

Sta. 1+50

F-4.6'  
El. 186.7'

TOILET

TRAILER

WATER TANK

CONSTRUCT  
DIVERSION  
DITCH

Sta. 0+00

C-3.6'  
El. 194.9'

### NOTES:

Elev. Ungraded Ground At Loc. Stake = 5192.4'  
FINISHED GRADE ELEV. AT LOC. STAKE = 5191.3'

UINTAH ENGINEERING & LAND SURVEYING  
86 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

# Kerr-McGee Oil & Gas Onshore LP

FIGURE #2

## TYPICAL CROSS SECTIONS FOR



NBU #1021-19E

SECTION 19, T10S, R21E, S.L.B.&M.

2146' FNL 879' FWL

1" = 20'  
X-Section  
Scale  
1" = 50'

DATE: 11-08-06  
Drawn By: S.L.



### NOTE:

Topsoil should not be  
Stripped Below Finished  
Grade on Substructure Area.

### \* NOTE:

FILL QUANTITY INCLUDES  
5% FOR COMPACTION

### APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,870 Cu. Yds.
Remaining Location	= 12,050 Cu. Yds.
<b>TOTAL CUT</b>	<b>= 13,440 CU.YDS.</b>
<b>FILL</b>	<b>= 5,680 CU.YDS.</b>

EXCESS MATERIAL	= 7,760 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,260 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation)	= 4,500 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 02/02/2007

API NO. ASSIGNED: 43-047-39006

WELL NAME: NBU 1021-19E

OPERATOR: KERR-MCGEE OIL & GAS ( N2995 )

CONTACT: SHEILA UPCHEGO

PHONE NUMBER: 435-781-7024

**PROPOSED LOCATION:**

SWNW 19 100S 210E

SURFACE: 2146 FNL 0879 FWL

BOTTOM: 2146 FNL 0879 FWL

COUNTY: UINTAH

LATITUDE: 39.93461 LONGITUDE: -109.6004

UTM SURF EASTINGS: 619588 NORTHINGS: 4421228

FIELD NAME: NATURAL BUTTES ( 630 )

INSPECT LOCATN BY: / /

**Tech Review**

**Initials**

**Date**

Engineering

DLD

2/27/07

Geology

Surface

LEASE TYPE: 3 - State

LEASE NUMBER: ML-22792

SURFACE OWNER: 3 - State

PROPOSED FORMATION: WSMVD

COALBED METHANE WELL? NO

**RECEIVED AND/OR REVIEWED:**

☒ Plat

☒ Bond: Fed[] Ind[] Sta[] Fee[]  
(No. 22013542 )

☒ Potash (Y/N)

☒ Oil Shale 190-5 (B) or 190-3 or 190-13

☒ Water Permit

(No. 43-8496 )

☒ RDCC Review (Y/N)

(Date: )

☒ Fee Surf Agreement (Y/N)

☒ Intent to Commingle (Y/N)

**LOCATION AND SITING:**

\_\_\_ R649-2-3.

Unit: NATURAL BUTTES

\_\_\_ R649-3-2. General

Siting: 460' From Qtr/Qtr & 920' Between Wells

\_\_\_ R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 17314

Eff Date: 12-2-1999

Siting: 460' v u lary f l u n t u m n o u s

\_\_\_ R649-3-11. Directional Drill

COMMENTS:

Needs Permit (02-13-07)

STIPULATIONS:

1- STATEMENT OF BASIS

2- OIL SHALE

3- Surface Csg Cont Step





# Application for Permit to Drill

## Statement of Basis

2/21/2007

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
232	43-047-39006-00-00		GW	S	No
<b>Operator</b>	KERR-MCGEE OIL & GAS ONSHORE, LP	<b>Surface Owner-APD</b>			
<b>Well Name</b>	NBU 1021-19E	<b>Unit</b>			
<b>Field</b>	UNDESIGNATED	<b>Type of Work</b>			
<b>Location</b>	SWNW 19 10S 21E S 0 F L 0 F L GPS Coord (UTM) 619588E 4421228N				

### Geologic Statement of Basis

Kerr McGee proposes to set 2,000' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 5,200'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 19. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought up above the base of the moderately saline ground water to isolate it from fresher waters uphole.

Brad Hill  
APD Evaluator

2/21/2007  
Date / Time

### Surface Statement of Basis

The general area is within the Cottonwood Wash Drainage. The area is characterized by rolling hills and benches, which are frequently intersected by somewhat gentle draws, which flow into Cottonwood Wash. The draws are occasionally rimmed with steep side hills, which have exposed sand stone bedrock cliffs along the rims. Cottonwood Wash is an ephemeral drainage, which drains northerly approximately 11 miles to the White River. No seeps, springs or streams exist in the area.

This location is approximately 16 miles southeast of Ouray, Ut. and is accessed by the Seep Ridge Road then by existing or planned oil field development roads to within 0.4 miles of the site, which will require up-grading and new construction.

The north end of the proposed location will be cut into a gentle to moderately sloping ridge which runs to the north and extends into a gentle sloping flat. A swale enters the location from the northwest and is planned to be diverted south around the pad.

Both the surface and minerals are owned by SITLA. Jim Davis represented SITLA at the pre-site investigation. Mr. Davis had no concerns pertaining to this location. The selected location appears to be the best site for drilling and operating a well in the immediate area.

Floyd Bartlett  
Onsite Evaluator

2/13/2007  
Date / Time

### Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 20 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** KERR-MCGEE OIL & GAS ONSHORE, LP  
**Well Name** NBU 1021-19E  
**API Number** 43-047-39006-0 **APD No** 232 **Field/Unit** UNDESIGNATED  
**Location:** 1/4,1/4 SWNW **Sec** 19 **Tw** 10S **Rng** 21E 0 FL 0 FL  
**GPS Coord (UTM)** 619586 4421229 **Surface Owner**

### **Participants**

Floyd Bartlett and David Hackford (DOGM), Jim Davis (SITLA), Carroll Estes, Tony Kznick, and Clay Einerson (Kerr McGee), David Kay (Uintah Engineering and Land Surveying), and Ben Williams (UDWR)

### **Regional/Local Setting & Topography**

The general area is within the Cottonwood Wash Drainage. The area is characterized by rolling hills and benches, which are frequently intersected by somewhat gentle draws, which flow into Cottonwood Wash. The draws are occasionally rimmed with steep side hills, which have exposed sand stone bedrock cliffs along the rims. Cottonwood Wash is an ephemeral drainage, which drains northerly approximately 11 miles to the White River. No seeps, springs or streams exist in the area.

This location is approximately 16 miles southeast of Ouray, Ut. and is accessed by the Seep Ridge Road then by existing or planned oil field development roads to within 0.4 miles of the site, which will require up-grading and new construction.

The north end of the proposed location will be cut into a gentle to moderately sloping ridge which runs to the north and extends into a gentle sloping flat. A swale enters the location from the northwest and is planned to be diverted south around the pad.

### **Surface Use Plan**

#### **Current Surface Use**

Grazing  
Recreational  
Wildlfe Habitat

#### **New Road**

<b>Miles</b>	<b>Well Pad</b>		<b>Src Const Material</b>	<b>Surface Formation</b>
0.4	<b>Width</b> 278	<b>Length</b> 350	Onsite	UNTA

**Ancillary Facilities** N

### **Waste Management Plan Adequate? Y**

### **Environmental Parameters**

**Affected Floodplains and/or Wetland** N

#### **Flora / Fauna**

Snow covered the vegetation on the area. Identifiable vegetation consisted of Gardner saltbush, shadscale, greasewood, and black sage. Vegetation is sparse.

Antelope, cattle, rabbits, coyotes, and small mammals, birds and raptors.

#### **Soil Type and Characteristics**

Moderately deep gravely sandy loam.

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required Y

Around the south and west side of the pad.

Berm Required? N

Erosion Sedimentation Control Required? N

Paleo Survey Run? Y      Paleo Potential Observed? N      Cultural Survey Run? Y      Cultural Resources? N

### Reserve Pit

Site-Specific Factors		Site Ranking
Distance to Groundwater (feet)	>200	0
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	300 to 1320	10
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	<10	0
Affected Populations	<10	0
Presence Nearby Utility Conduits	Not Present	0
Final Score		25    1    Sensitivity Level

### Characteristics / Requirements

The proposed reserve pit is 70' x 150' x 10' deep located in a cut on the north west corner of the location. A 20 mil liner with a felt sub-liner is planned by Kerr McGee.

Closed Loop Mud Required? N      Liner Required? Y      Liner Thickness 20      Pit Underlayment Required? Y

### Other Observations / Comments


Ben Williams representing the UDWR stated the area is classified as yearlong critical habitat for antelope. He stated that the lack of water not forage is the limiting factor affecting the herd in the area. He recommended no restrictions for antelope. No other wildlife is expected to be significantly affected. He gave Jim Davis of SITLA and Carroll Estes of Kerr McGee a copy of his wildlife evaluation and a UDWR recommended seed mix to be used when revegetating the location.

The area was covered with snow. ATV's were used to access the site.

Floyd Bartlett  
Evaluator

2/13/2007  
Date / Time

Casing Schematic



Well name:

**2007-02 Kerr McGee NBU 1021-19E**Operator: **Kerr McGee Oil & Gas Onshore L.P.**String type: **Surface**

Project ID:

**43-047-39006**Location: **Uintah County, Utah****Design parameters:****Collapse**Mud weight: 8.400 ppg  
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 103 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 1,507 ft

**Burst**Max anticipated surface  
pressure: 1,760 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 2,000 psi

No backup mud specified.

**Tension:**8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 1,753 ft

**Non-directional string.****Re subsequent strings:**Next setting depth: 9,620 ft  
Next mud weight: 11.500 ppg  
Next setting BHP: 5,747 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 2,000 ft  
Injection pressure: 2,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2000	9.625	32.30	H-40	ST&C	2000	2000	8.876	883.7
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	873	1370	1.570	2000	2270	1.14	57	254	4.49 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & MineralsPhone: (801) 538-5357  
FAX: (801) 359-3940Date: February 22, 2007  
Salt Lake City, Utah**Remarks:**Collapse is based on a vertical depth of 2000 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.  
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:

**2007-02 Kerr McGee NBU 1021-19E**Operator: **Kerr McGee Oil & Gas Onshore L.P.**String type: **Production**

Project ID:

**43-047-39006**Location: **Uintah County, Utah****Design parameters:****Collapse**

Mud weight: 11.500 ppg

Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 210 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,500 ft

Cement top: Surface

**Burst**

Max anticipated surface

pressure: 3,631 psi

Internal gradient: 0.220 psi/ft

Calculated BHP 5,747 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on buoyed weight.

Neutral point: 7,966 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	9620	4.5	11.60	I-80	LT&C	9620	9620	3.875	839.5
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	5747	6360	1.107	5747	7780	1.35	92	212	2.29 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & MineralsPhone: (801) 538-5357  
FAX: (801) 359-3940Date: February 22, 2007  
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 9620 ft, a mud weight of 11.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, Utah 84145-0155

### IN REPLY REFER TO:

3160  
(UT-922)

February 7, 2007

### Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2007 Plan of Development Natural Buttes Unit Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2007 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ Wasatch/MesaVerde)

43-047-39004	NBU 1021-19C	Sec. 19 T. 10S R. 21E	0620 FNL 1904 FWL
43-047-39005	NBU 1021-19D	Sec. 19 T. 10S R. 21E	0637 FNL 0755 FWL
43-047-39006	NBU 1021-19E	Sec. 19 T. 10S R. 21E	2146 FNL 0879 FWL
43-047-39007	NBU 1021-19K	Sec. 19 T. 10S R. 21E	2181 FSL 2092 FWL
43-047-39008	NBU 1021-19N	Sec. 19 T. 10S R. 21E	0462 FSL 1845 FWL
43-047-39009	NBU 1021-29L	Sec. 29 T. 10S R. 21E	1398 FSL 0190 FWL
43-047-39010	NBU 1021-29O	Sec. 29 T. 10S R. 21E	0615 FSL 2115 FEL
43-047-39011	NBU 1021-29N	Sec. 29 T. 10S R. 21E	0250 FSL 1764 FWL
43-047-39012	NBU 1021-29J	Sec. 29 T. 10S R. 21E	1532 FSL 2192 FEL
43-047-39013	NBU 1021-29K	Sec. 29 T. 10S R. 21E	1804 FSL 2143 FWL
43-047-39014	NBU 1021-29I	Sec. 29 T. 10S R. 21E	2060 FSL 0962 FEL
43-047-39015	NBU 1021-29G	Sec. 29 T. 10S R. 21E	2090 FNL 1960 FEL
43-047-39016	NBU 1021-29F	Sec. 29 T. 10S R. 21E	1718 FNL 1529 FWL
43-047-39017	NBU 1021-29E	Sec. 29 T. 10S R. 21E	2635 FNL 1010 FWL
43-047-39018	NBU 1021-29C	Sec. 29 T. 10S R. 21E	0476 FNL 2501 FWL
43-047-39019	NBU 1021-29A	Sec. 29 T. 10S R. 21E	0170 FNL 0627 FEL
43-047-39020	NBU 1021-30I	Sec. 30 T. 10S R. 21E	2131 FSL 0387 FEL
43-047-39021	NBU 1021-30J	Sec. 30 T. 10S R. 21E	1901 FSL 1827 FEL
43-047-39022	NBU 1021-30K	Sec. 30 T. 10S R. 21E	1398 FSL 2686 FWL
43-047-39023	NBU 1021-30L	Sec. 30 T. 10S R. 21E	1602 FSL 0980 FWL
43-047-39024	NBU 1021-30M	Sec. 30 T. 10S R. 21E	0612 FSL 0462 FWL

Page 2

43-047-39025 NBU 1021-30N Sec. 30 T. 10S R. 21E 0942 FSL 1876 FWL  
43-047-39026 NBU 1021-32A Sec. 32 T. 10S R. 21E 0646 FNL 0955 FEL  
43-047-39027 NBU 1021-32B Sec. 32 T. 10S R. 21E 0837 FNL 2117 FEL  
43-047-39028 NBU 1021-32C Sec. 32 T. 10S R. 21E 0664 FNL 1840 FWL  
43-047-39029 NBU 1021-32F Sec. 32 T. 10S R. 21E 1909 FNL 2165 FWL  
43-047-39001 NBU 1021-01G Sec. 01 T. 10S R. 21E 2660 FSL 1765 FEL  
43-047-39002 NBU 1021-01O Sec. 01 T. 10S R. 21E 0245 FSL 2619 FEL  
43-047-39003 NBU 1021-01P Sec. 01 T. 10S R. 21E 0888 FSL 1309 FEL  
43-047-39030 NBU 1022-18A Sec. 18 T. 10S R. 22E 1007 FNL 0512 FEL  
43-047-39031 NBU 1022-24I Sec. 24 T. 10S R. 22E 2045 FSL 1166 FEL  
43-047-39032 NBU 1022-25B Sec. 25 T. 10S R. 22E 0403 FNL 1971 FEL  
43-047-39033 NBU 1022-25H Sec. 25 T. 10S R. 22E 2604 FNL 0825 FEL

Our records indicate the NBU 1022-25H is closer than 460 feet from the Natural Buttes Unit boundary (approximately 36 feet).

We have no objections to permitting the wells so long as the unit operator receives an exception to the locating and siting requirements of the State of Utah (R649-3-2).

/s/ Michael L. Coulthard

bcc: File – Natural Buttes Unit  
Division of Oil Gas and Mining  
Central Files  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:2-7-07



**From:** Ed Bonner  
**To:** Mason, Diana  
**Date:** 2/27/2007 8:48 AM  
**Subject:** Well Clearance

**CC:** Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil  
The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

Kerr McGee Oil & Gas Onshore LP  
NBU 1021-19C (API 43 047 39004)  
NBU 1021-19D (API 43 047 39005)  
NBU 1021-19E (API 43 047 39006)  
NBU 1021-19K (API 43 047 39007)  
NBU 1021-19N (API 43 047 39008)  
NBU 1022-18A (API 43 047 39030)

If you have any questions regarding this matter please give me a call.



**State of Utah**

**Department of  
Natural Resources**

MICHAEL R. STYLER  
*Executive Director*

**Division of  
Oil, Gas & Mining**

JOHN R. BAZA  
*Division Director*

JON M. HUNTSMAN, JR.  
*Governor*

GARY R. HERBERT  
*Lieutenant Governor*

February 28, 2007

Kerr-McGee Oil & Gas Onshore LP  
1368 S 1200 E  
Vernal, UT 84078

Re: Natural Buttes Unit 1021-19E Well, 2146' FNL, 879' FWL, SW NW, Sec. 19,  
T. 10 South, R. 21 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39006.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Uintah County Assessor (via e-mail)  
SITLA  
Bureau of Land Management, Vernal District Office

Operator: Kerr-McGee Oil & Gas Onshore LP  
Well Name & Number Natural Buttes Unit 1021-19E  
API Number: 43-047-39006  
Lease: ML-22792

Location: SW NW Sec. 19 T. 10 South R. 21 East

### Conditions of Approval

#### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### 2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office  
(801) 733-0983 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office  
(801) 733-0983 home

#### 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.
7. Surface casing shall be cemented to the surface.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL		OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22792
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP				6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR:		1368 SOUTH 1200 EAST VERNAL UT 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
		PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 1021-19E
4. LOCATION OF WELL				9. API NUMBER: 4304739006
FOOTAGES AT SURFACE: 2146'FNL, 879'FWL LOT 2				10. FIELD AND POOL, OR WILDCAT:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E				COUNTY: UINTAH
				STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR REQUESTS AUTHORIZATION TO CHANGE THE ROUTE OF THE PIPELINE FROM APPROXIMATELY 3450' AND 1415' +/- OF 4" STEEL PIPELINE TO APPROXIMATELY 9500' +/- OF 4" STEEL PIPELINE THE PIPELINE WILL STAY ON STATE LANDS IN SEC. 18, & 17 T10S, R21E THE PIPELINE WILL TIE-IN TO AN EXISTING PIPELINE IN SECTION 17, T10S, R21E.


REFER TO THE ATTACHED REVISED TOPO MAP D FOR PIPELINE PLACEMENT.

COPY SENT TO OPERATOR

Date: 2-16-07  
Initials: CHD

RECEIVED  
JUL 02 2007


DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE 	DATE 6/25/2007

(This space for State use only)

Accepted by the  
Utah Division of  
Oil, Gas and Mining  
For Record Only





**APPROXIMATE TOTAL 8" PIPELINE DISTANCE = 9,500' +/-**

**LEGEND:**

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)



**Kerr-McGee Oil & Gas Onshore LP**

**NBU #1021-19E**  
**SECTION 19, T10S, R21E, S.L.B.&M.**  
**2146' FNL 879' FWL**



**Utah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC**  
**MAP**

**11 03 06**  
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 02-21-07





STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22792
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 1021-19E
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2146'FNL, 879'FWL (LOT 2)		9. API NUMBER: 4304739006
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>APD EXTENSION</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR REQUESTS AUTHORIZATION FOR A ONE YEAR EXTENSION FOR THE SUBJECT WELL LOCATION. SO THAT THE DRILLING OPERATIONS MAY BE COMPLETED. THE ORIGINAL APD WAS APPROVED BY THE DIVISION OF OIL, GAS AND MINING ON FEBRUARY 28, 2007.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 02-25-08  
By: [Signature]

COPY SENT TO OPERATOR

Date: 2-26-2008

Initials: KS

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE <u>[Signature]</u>	DATE 2/6/2008

(This space for State use only)

RECEIVED

FEB 25 2008

DIV. OF OIL, GAS & MINING

**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 4304739006  
**Well Name:** NBU 1021-19E  
**Location:** SW/NW LOT 2, SEC. 19, T10S, R21E  
**Company Permit Issued to:** KERR McGEE OIL AND GAS ONSHORE LP  
**Date Original Permit Issued:** 2/28/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

  
Signature

2/6/2008

Date

Title: SENOIR LAND ADMIN SPECIALIST

Representing: KERR-McGEE OIL & GAS ONSHORE LP

**RECEIVED**  
**FEB 25 2008**  
DIV. OF OIL, GAS & MINING



## DIVISION OF OIL, GAS AND MINING

### **SPUDDING INFORMATION**

Name of Company: KERR-McGEE OIL & GAS ONSHORE, LP

Well Name: NBU 1021-19E

Api No: 43-047-39006 Lease Type: STATE

Section 19 Township 10S Range 21E County UINTAH

Drilling Contractor PETE MARTIN DRLG RIG # BUCKET

### **SPUDDED:**

Date 06/22/08

Time 8:00 AM

How DRY

**Drilling will Commence:** \_\_\_\_\_

Reported by LEW WELDON

Telephone # (435) 828-7035

Date 06/24//08 Signed CHD

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995  
Address: 1368 SOUTH 1200 EAST  
city VERNAL  
state UT zip 84078 Phone Number: (435) 781-7024

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304737757	NBU 920-20L		NWSW	20	9S	20E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
B	99999	2900	6/23/2008		6/30/08		
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 06/23/2008 AT 1100 HRS.							

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304739006	NBU 1021-19E		SWNW	19	10S	21E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
B	99999	2900	6/22/2008		6/30/08		
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 06/22/2008 AT 0800 HRS.							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

SHEILA UPCHEGO

Name (Please Print) Sheila Upchego  
Signature Sheila Upchego  
SENIOR LAND SPECIALIST 6/24/2008  
Title Date

**RECEIVED**

**JUN 24 2008**

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22792
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 1021-19E
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2146'FNL, 879'FWL LOT 2		9. API NUMBER: 4304739006
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: WELL SPUD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE.  
CMT W/28 SX READY MIX.

SPUD WELL LOCATION ON 06/22/2008 AT 0800 HRS.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE 	DATE 6/24/2008

(This space for State use only)

RECEIVED

JUN 26 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22792
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2146'FNL, 879'FWL LOT 2 QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E		8. WELL NAME and NUMBER: NBU 1021-19E
		9. API NUMBER: 4304739006
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: SET SURFACE CSG
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PROPETRO AIR RIG ON 06/23/2008. DRILLED 12 1/4" SURFACE HOLE TO 2060'. RAN 9 5/8" 36# J-55 SURFACE CSG. LEAD CMT W/175 SX HIFILL CLASS G @11.0 PPG 3.82 YIELD. TAILED CMT W/200 SX PREM CLASS G @15.8 PPG 1.15 YIELD. GOOD RETURNS THROUGH OUT JOB 27 +/- BBL CMT TO PIT. RAN 200' OF 1" PIPE. CMT W/100 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN 1" PIPE GOOD CMT TO SURFACE AND FELL BACK. TOP OUT W/75 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN BACKSIDE GOOD CMT TO SURFACE HOLE STAYED FULL.

WORT.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE 	DATE 6/24/2008

(This space for State use only)

RECEIVED  
JUN 30 2008  
DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22792
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 1021-19E
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2146'FNL, 879'FWL LOT 2		9. API NUMBER: 4304739006
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: FINAL DRILLING OPERATIONS
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

FINISHED DRILLING FROM 2060' TO 9680' ON 08/05/2008. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. LEAD CMT W/440 SX PREM LITE II @11.5 PPG 2.82 YIELD. TAILED CMT W/1800 SX 50/50 POZ @14.3 PPG 1.31 YIELD. DISPLACE W/150 BBLS CLAY TREAT NO RETURNS DURING JOB UNTIL START OF DISPLACEMENT 29 BBLS CMT BACK BUMP PLUG @3677 PSI HELD. NIPPLE DOWN SET SLIPS W/70K CUT OFF CSG. CLEAN PITS.

RELEASED PIONEER RIG ON 08/07/2008 AT 1600 HRS.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 8/8/2008

(This space for State use only)

RECEIVED  
AUG 11 2008  
DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
KERR MCGEE OIL & GAS ONSHORE LP

3. ADDRESS OF OPERATOR:  
1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-7024

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2146'FNL, 879'FWL LOT 2

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E

5. LEASE DESIGNATION AND SERIAL NUMBER:  
ML-22792

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:  
UNIT #891008900A

8. WELL NAME and NUMBER:  
NBU 1021-19E

9. API NUMBER:  
4304739006

10. FIELD AND POOL, OR WILDCAT:  
NATURAL BUTTES

COUNTY: UINTAH

STATE:  
UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>PRODUCTION</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>START-UP</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 08/23/2008 AT 10:00 AM.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 8/26/2008

(This space for State use only)

RECEIVED

SEP 09 2008

DIV. OF OIL, GAS & MINING

Wins No.: 95182

NBU 1021-19E

## Well Operations Summary Long

Operator KERR MCGEE OIL & GAS ONSHORE LP	FIELD NAME NATURAL BUTTES	SPUD DATE 06/22/2008	GL 5,192	KB 5208	ROUTE
API 4304739006	STATE UTAH	COUNTY UINTAH	DIVISION ROCKIES		
Long/Lat.: 39.93457 / 109.60110		Q-Q/Sect/Town/Range: SWNW / 19 / 10S / 21E		Footages: 2,146.00' FNL 879.00' FWL	

## Wellbore: NBU 1021-19E

MTD 9,680	TVD 9,676	PBMD	PBTVD
--------------	--------------	------	-------

EVENT INFORMATION: EVENT ACTIVITY: DRILLING START DATE: 6/22/2008 AFE NO.: 2011273  
 OBJECTIVE: DEVELOPMENT END DATE:  
 OBJECTIVE 2: VERTICAL WELL DATE WELL STARTED PROD.:  
 REASON: DRILL PROD HOLE Event End Status:

RIG OPERATIONS:	Begin Mobilization	Rig On Location	Rig Charges	Rig Operation Start	Finish Drilling	Rig Release	Rig Off Location
PIONEER 38 / 38	07/21/2008	07/21/2008	07/21/2008	07/23/2008	08/05/2008	08/07/2008	08/07/2008

Date	Time Start-End	Duration (hr)	Phase	Code	Subcode	P/U	Operation
------	----------------	---------------	-------	------	---------	-----	-----------

6/22/2008 SUPERVISOR: LEW WELDON JO MD: 56

8:00 - 15:00	7.00	DRLCON	02	P	MOVE IN AND RIG UP BUCKET RIG SPUD WELL @ 0800 HR 6/22/08 DRILL AND SET 40' OF SCHEDULE 10 PIPE DRILL RODENT HOLES FOR RIG 38 BLM AND STATE NOTFIED OF SPUD
--------------	------	--------	----	---	--

6/23/2008 SUPERVISOR: LEW WELDON MD: 510  
 17:00 - 0:00 7.00 DRLSUR 02 P MOVE IN AND RIG UP AIR RIG SPUD WELL @ 1700 HR 6/23/08  
 DA AT REPORT TIME

6/24/2008 SUPERVISOR: LEW WELDON MD: 1,830  
 0:00 - 12:00 12.00 DRLSUR 02 P RIG DRILLING AHEAD NO WATER 930'  
 12:00 - 0:00 12.00 DRLSUR 02 P RIG DRILLING AHEAD NO WATER 1830'

6/25/2008 SUPERVISOR: LEW WELDON MD: 2,060  
 0:00 - 15:00 15.00 DRLSUR 02 P RIG T/D @ 2060' CONDITION HOLE 1 HR  
 15:00 - 18:00 3.00 DRLSUR 05 P TRIP DP OUT OF HOLE  
 18:00 - 21:00 3.00 DRLSUR 11 P RUN 2016' OF 9 5/8 CSG AND 200' OF 1" PIPE RIG DOWN AIR RIG  
 21:00 - 22:00 1.00 DRLSUR 15 P CEMENT 1ST STAGE WITH 175 SKS LEAD @ 11# 3.82 23 GAL/SK  
 AND 200 SKS TAIL @ 15.8# 1.15 5.0 GAL/SK GOOD RETURNS  
 THRUOUT JOB + - 27 BBL LEAD CMT TO PIT  
 22:00 - 22:30 0.50 DRLSUR 15 P 1ST TOP JOB 100 SKS DOWN 1" PIPE GOOD CMT TO SURFACE  
 AND FELL BACK WOC

Wins No.: 95182		NBU 1021-19E					API No.: 4304739006	
	22:00 - 22:30	0.50	DRLSUR	15	P	1ST TOP JOB 100 SKS DOWN 1" PIPE GOOD CMT TO SURFACE AND FELL BACK WOC		
	22:30 - 23:30	1.00	DRLSUR	15	P	2ND TOP JOB 75 SKS DOWN BS GOOD CMT TO SURFACE AND STATYED AT SURFACE		
	23:30 - 23:30	0.00	DRLSUR			NO VISIBLE LEAKS PIT 1/4 FULL WORT		
7/20/2008	SUPERVISOR: LEW WELDON					MD: 2,060		
	6:00 - 0:00	18.00	RDMO	01	E	P	RDRT F/MOVE TO 19E	
7/21/2008	SUPERVISOR: KENNY MORRIS					MD: 2,060		
	0:00 - 7:00	7.00	RDMO	01	E	P	PREP F/MOVE	
	7:00 - 18:00	11.00	MIRU	01	A	P	MOVE W/RW JONES,	
	18:00 - 0:00	6.00	MIRU	01	B	P	RURT	
7/22/2008	SUPERVISOR: KENNY MORRIS					MD: 2,060		
	0:00 - 11:00	11.00	MIRU	01	B	P	RURT,CHANGE KELLY HOSE,RAISE DERRICK @DAYLITE,	
	11:00 - 18:00	7.00	MIRU	06	D	P	SLIP NEW DRLG LINE ON CARRIER,SLIP NEW THRU BLOCKS	
	18:00 - 0:00	6.00	MIRU	01	B	P	RURT,,FLOOR,KELLY,SWIVAL,,FUNCTION TEST BOP,GENERAL RIG EQUIPMENT	
7/23/2008	SUPERVISOR: KENNY MORRIS					MD: 2,102		
	0:00 - 3:00	3.00	PRSPD	13	A	P	NUBOP,FLARE LINES	
	3:00 - 9:30	6.50	PRSPD	13	A	P	TEST BOP,ANN 2500,CSG 1500,RAMS& CHOKE 5K	
	9:30 - 14:00	4.50	PRSPD	05	A	P	RU.& P/U BHA ,,DRILL PIPE,	
	14:00 - 21:00	7.00	PRSPD	07	B	S	DROP SPINNERS TORQUE KELLY,PULL&REINSTALL LINERS IN BOTH PUMPS,GASKETS LEFT OUT	
	21:00 - 23:30	2.50	PRSPD	02	F	P	DRILL CEMENT & FE F/1850 TO 2060'	
	23:30 - 0:00	0.50	DRLPRO	02	B	P	DRILL NEW 7.875 HOLE F/2060 TO 2102	
7/24/2008	SUPERVISOR: KENNY MORRIS					MD: 3,190		
	0:00 - 0:30	0.50	DRLPRO	09	A	P	SURVEY@2031=1	



Wins No.: 95182		NBU 1021-19E						API No.: 4304739006
	0:00 - 0:30	0.50	DRLPRO	09	A	P	SURVEY@2031=1	
	0:30 - 6:00	5.50	DRLPRO	02	B	P	DRILL F/2102 TO 2482,AVG 69 WT 8.4 /27	
	6:00 - 11:00	5.00	DRLPRO	07	B	S	POOH TO SHOE CHANGE KELLY HOSE, TIH	
	11:00 - 12:00	1.00	DRLPRO	02	B	P	DRILL F/2482' TO 2544,AVG 62 WT 8.7/27	
	12:00 - 12:30	0.50	DRLPRO	09	A	P	SURVEY@2474=1	
	12:30 - 13:00	0.50	DRLPRO	06	A	P	RIG SERVICE	
	13:00 - 23:00	10.00	DRLPRO	02	B	P	DRILL F/2544 TO 3148,AVG 60 WT 8.9/33	
	23:00 - 23:30	0.50	DRLPRO	09	A	P	SURVEY@3078=1.5	
	23:30 - 0:00	0.50	DRLPRO	02	B	P	DRILL F/3148 TO 3190,AVG 42 WT 8.9/34	
7/25/2008	SUPERVISOR: KENNY MORRIS							MD: 4,386
	0:00 - 9:00	9.00	DRLPRO	02	B	P	DRILL F/3190 TO 3593,AVG 45 WT 8.6/36	
	9:00 - 9:30	0.50	DRLPRO	06	A	P	RIG SERVICE	
	9:30 - 10:00	0.50	DRLPRO	09	A	P	SURVEY@ 3523=1	
	10:00 - 14:00	4.00	DRLPRO	02	B	P	DRILL F/3593 TO 3878,AVG71 WT 8.8/38	
	14:00 - 14:30	0.50	DRLPRO	07	B	P	TIGHTEN SWIVEL PACKING	
	14:30 - 19:30	5.00	DRLPRO	02	B	P	DRILL F/3878 TO 4100,AVG 44 8.9/38	
	19:30 - 20:00	0.50	DRLPRO	09	A	P	SURVEY@ 4030=2	
	20:00 - 0:00	4.00	DRLPRO	02	B	P	DRILL F/4100 TO 4386AVG 71 WT 8.9/38	
7/26/2008	SUPERVISOR: KENNY MORRIS							MD: 5,404
	0:00 - 10:30	10.50	DRLPRO	02	B	P	DRILL F/4386 TO 5025,AVG 60 WT 9.4/40	
	10:30 - 11:00	0.50	DRLPRO	06	A	P	RIG SERVICE	
	11:00 - 11:30	0.50	DRLPRO	09	A	P	SURVEY@4955=3	

Wins No.: 95182		NBU 1021-19E						API No.: 4304739006
	11:00 - 11:30	0.50	DRLPRO	09	A	P	SURVEY@4955=3	
	11:30 - 0:00	12.50	DRLPRO	02	B	P	DRILL F/5025 TO 5404,AVG 30 WT 9.8 44	
7/27/2008	SUPERVISOR: KENNY MORRIS							MD: 6,038
	0:00 - 11:30	11.50	DRLPRO	02	B	P	DRILL F/5404 TO 5752,AVG 30 WT 10/46	
	11:30 - 12:00	0.50	DRLPRO	06	A	P	RIG SERVICE	
	12:00 - 12:30	0.50	DRLPRO	09	A	P	SURVEY@ 5682=2	
	12:30 - 0:00	11.50	DRLPRO	02	B	P	DRILL F/5752 TO 6038,AVG 26 WT 10.2/44	
7/28/2008	SUPERVISOR: KENNY MORRIS							MD: 6,560
	0:00 - 17:00	17.00	DRLPRO	02	B	P	DRILL F/6038 TO 6418,AVG 23 WT 10.4/44	
	17:00 - 17:30	0.50	DRLPRO	06	A	P	RIG SERVICE	
	17:30 - 0:00	6.50	DRLPRO	02	B	P	DRILL F/6418 TO 6560,AVG 23 WT 10.5/42	
7/29/2008	SUPERVISOR: BRAD PETERSEN							MD: 6,780
	0:00 - 9:00	9.00	DRLPRO	02	B	P	DRILL F/ 6560' TO 6702' ( 142' 15.7' HR ) WT 10.5/45	
	9:00 - 9:30	0.50	DRLPRO	04	C	P	MIX & PUMP PILL	
	9:30 - 14:30	5.00	DRLPRO	05	A	P	TOOH W/ BIT #2 L/D MOTOR ,NO PROBLEMS ON TRIP	
	14:30 - 20:00	5.50	DRLPRO	05	A	P	P/U BIT #2 & NEW MOTOR TIH,FILL PIPE @ SHOE,NO FILL	
	20:00 - 0:00	4.00	DRLPRO	02	B	P	DRLG F/ 6700' TO 6780' ( 80' 20' HR ) WT 10.7/43	
7/30/2008	SUPERVISOR: BRAD PETERSEN							MD: 7,220
	0:00 - 1:00	1.00	DRLPRO	02	B	P	DRLG F/ 6780' TO 6795' ( 15' HR ) WT 10.7/43	
	1:00 - 1:30	0.50	DRLPRO	09	A	P	SURVEY @ 6725' 1.25 DEG.	
	1:30 - 12:00	10.50	DRLPRO	02	B	P	DRLG F/ 6795' TO 6986' ( 191' 18.1' HR ) WT 10.7/43	
	12:00 - 12:30	0.50	DRLPRO	06	A	P	RIG SERVICE	

	12:30 - 0:00	11.50	DRLPRO	02	B	P	DRLG F/ 6986' TO 7220' ( 234'20.3' HR ) WT 10.8/44	
7/31/2008	<u>SUPERVISOR:</u> BRAD PETERSEN							<u>MD:</u> 7,723
	0:00 - 13:00	13.00	DRLPRO	02	B	P	DRLG F/ 7220' TO 7497' ( 277' 21.3' HR ) WT 11.8/44	
	13:00 - 13:30	0.50	DRLPRO	06	A	P	RIG SERVICE	
	13:30 - 0:00	10.50	DRLPRO	02	B	P	DRLG F/ 7497' TO 7723' ( 226' 21.5' HR ) WT 10.8/44	
8/1/2008	<u>SUPERVISOR:</u> BRAD PETERSEN							<u>MD:</u> 8,070
	0:00 - 11:30	11.50	DRLPRO	02	B	P	DRLG F/ 7723' TO 7975' ( 252' 21.9' HR ) WT 10.8/43	
	11:30 - 12:00	0.50	DRLPRO	06	A	P	RIG SERVICE	
	12:00 - 18:00	6.00	DRLPRO	02	B	P	DRLG F/ 7975' TO 8070' ( 95' 15.8' HR ) WT 11/46	
	18:00 - 19:00	1.00	DRLPRO	04	C	P	MIX & PUMP PILL,DROP SURVEY	
	19:00 - 0:00	5.00	DRLPRO	05	A	P	TOOH W/ BIT #2 L/D BIT & MOTOR	
8/2/2008	<u>SUPERVISOR:</u> BRAD PETERSEN							<u>MD:</u> 8,552
	0:00 - 5:00	5.00	DRLPRO	05	A	P	CHANGE BIT & MOTOR,TIH W/BIT #3,NO PROBLEMS,NO FILL	
	5:00 - 12:30	7.50	DRLPRO	02	B	P	DRLG F/ 8070' TO 8259' (189' 25.2' HR ) WT 11.1/42	
	12:30 - 13:00	0.50	DRLPRO	06	A	P	RIG SERVICE	
	13:00 - 0:00	11.00	DRLPRO	02	B	P	DRLG F/ 8259' TO 8552' ( 293' 26.6' HR ) WT11.3/49	
8/3/2008	<u>SUPERVISOR:</u> BRAD PETERSEN							<u>MD:</u> 8,984
	0:00 - 15:00	15.00	DRLPRO	02	B	P	DRLG F/ 8552' TO 8862' ( 310' 20.6' HR ) WT 11.4/45	
	15:00 - 15:30	0.50	DRLPRO	06	A	P	RIG SERVICE	
	15:30 - 0:00	8.50	DRLPRO	02	B	P	DRLG F/ 8862' TO 8984' ( 122' 14.3' HR ) WT 11.4/44	
8/4/2008	<u>SUPERVISOR:</u> BRAD PETERSEN							<u>MD:</u> 9,160
	0:00 - 6:00	6.00	DRLPRO	02	B	P	DRLG F/ 8984' TO 9070' ( 86' 14.3' HR ) WT11.4/43	
	6:00 - 7:00	1.00	DRLPRO	04	C	P	CIRC,MIX & PUMP PILL	

Wins No.: 95182		NBU 1021-19E						API No.: 4304739006	
	6:00 - 7:00	1.00	DRLPRO	04	C	P	CIRC,MIX & PUMP PILL		
	7:00 - 12:00	5.00	DRLPRO	05	A	P	TOOH W/BIT #3,CHANGE BITS		
	12:00 - 14:00	2.00	DRLPRO	05	A	P	TIH W/ BIT #4 & BHA		
	14:00 - 15:30	1.50	DRLPRO	06	D	P	SLIP & CUT DRLG LINE		
	15:30 - 19:30	4.00	DRLPRO	05	A	P	FINISH TIH		
	19:30 - 20:30	1.00	DRLPRO	03	D	P	WASH 45' TO BTM,NO FILL		
	20:30 - 0:00	3.50	DRLPRO	02	B	P	DRLG F/ 9070' TO 9160' ( 90'16.3' HR ) WT 11.5/44		
8/5/2008	<u>SUPERVISOR:</u> BRAD PEDERSEN							<u>MD:</u>	9,680
	0:00 - 15:00	15.00	DRLPRO	02	B	P	DRLG F/ 9160'-9527' ( 367' 24.4' hr ) 11.7/46		
	15:00 - 15:30	0.50	DRLPRO	06	A	P	RIG SERVICE		
	15:30 - 19:30	4.00	DRLPRO	02	B	P	DRLG F/ 9527' TO 9680' TD ( 153' 38.2' HR ) WT 11.8/46,TD @ 19:30 8/5/2008		
	19:30 - 22:00	2.50	DRLPRO	04	C	P	CIRC F/ SHORT TRIP,PUMP PILL		
	22:00 - 23:00	1.00	DRLPRO	05	E	P	SHORT TRIP TO 8750' NO PROBLEMS		
	23:00 - 0:00	1.00	DRLPRO	04	C	P	CIRC F/ LDDP,SAFETY MEETING W/ & R/U TESCO		
8/6/2008	<u>SUPERVISOR:</u> BRAD PEDERSEN							<u>MD:</u>	9,680
	0:00 - 10:00	10.00	DRLPRO	05	A	P	LDDP,BREAK KELLY,LD BHA,PULL WEAR RING		
	10:00 - 16:30	6.50	DRLPRO	10	C	P	SAFETY MEETING W/ HALLIBURTON R/U & RUN QUAD COMBO TO 9679',R/D LOGGERS		
	16:30 - 0:00	7.50	DRLPRO	11	B	P	SAFETY MEETING W/ TESCO R/U & RUN 4.5" PROD CASING		
8/7/2008	<u>SUPERVISOR:</u> BRAD PEDERSEN							<u>MD:</u>	9,680
	0:00 - 2:00	2.00	DRLPRO	11	B	P	FINISH RUNNING 228 JTS 4.5,11.6,I-80 TO 9663'		
	2:00 - 3:00	1.00	DRLPRO	04	E	P	ATTEMPT TO CIRC F/ CMT PUMPED 150 BBLS NO RETURNS,BUILD VOLUME MIX LCM TO 5% PUMPED 150 BBLS NO RETURNS		

Wins No.: 95182		NBU 1021-19E					API No.: 4304739006
2:00 - 3:00	1.00	DRLPRO	04	E	P	ATTEMPT TO CIRC F/ CMT PUMPED 150 BBLS NO RETURNS,BUILD VOLUME MIX LCM TO 5% PUMPED 150 BBLS NO RETURNS	
3:00 - 5:30	2.50	DRLPRO	12	E	Z	WAIT ON BJ SERVICES DUE TO TRUCK BROKE DOWN ENROUTE TO LOCATION	
5:30 - 9:00	3.50	DRLPRO	15	A	P	SAFETY MEETING W/ BJ SERVICES R/U & PUMP 20 BBLS MUD CLEAN,20 BBLS SCAVENGER,440 SX LEAD,1800 SX TAIL DISPLACE W/ 150 BBLS CLAY TREAT,NO RETURNS DURING JOB UNTILSTART OF DISPLACMENT, 29 BBLS CMT BACK,BUMP PLUG @ 3677 PSI HELD,R/D BJ	
9:00 - 14:00	5.00	DRLPRO	13	A	S	NIPPLE DOWN SET SLIPS @ 70K,CUT OFF CASING	
14:00 - 16:00	2.00	DRLPRO	01	E	P	CLEAN PITS RELEASE RIG @ 16:00 8/7/2008 TO NBU 1021-13N	



<b>Wins No.: 95182</b>		<b>NBU 1021-19E</b>		<b>API No.: 4304739006</b>	
<b>EVENT INFORMATION:</b>		EVENT ACTIVITY: COMPLETION		START DATE: 8/18/2008	
		OBJECTIVE: DEVELOPMENT		END DATE:	
		OBJECTIVE 2: ORIGINAL		DATE WELL STARTED PROD.:	
		REASON: MV		Event End Status:	
<b>RIG OPERATIONS:</b>		Begin Mobilization	Rig On Location	Rig Charges	Rig Operation Start
					Finish Drilling
					Rig Release
					Rig Off Location
<b>MILES 2 / 2</b>					
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode
8/18/2008	<u>SUPERVISOR:</u> JEFF SAMUELS				
	7:00 - 17:00	10.00	COMP	31	I
					P
<p>7:00 A.M. HSM</p> <p>ROAD RIG &amp; EQUIP F/ NBU 921-14P TO LOC. MIRU, NDWH.</p> <p>NUBOPE. PREP &amp; TALLY 2 3/8" L-80 8RD 4.7# TBG. P/U 3 7/8"</p> <p>MILL, BIT SUB &amp; RIH P/U TBG OFF TRAILER TO 8284'. X-O POOH</p> <p>W/ TBG. EOT @ 4493'. SWI. SDFN</p>					
8/19/2008	<u>SUPERVISOR:</u> JEFF SAMUELS				
	7:00 - 18:00	11.00	COMP	36	B
					P
<p>7:00 A.M. HSM</p> <p>CONT TO POOH W/ TBG F/ 4493', L/D MILL &amp; BIT SUB. NDBOPE,</p> <p>NU FRAC VLV'S. MIRU B&amp;C QUICK TST. FILL CSG &amp; PSI TST</p> <p>CSG &amp; FRAC VLV'S TO 7500# (HELD). RDMO B&amp;C. MIRU</p> <p>CUTTERS. P/U 3 3/8" EXP PERF GUNS LOADED W/ 23 GM</p> <p>CHARGES. 4 SPF, 90 DEG PHASING &amp; RIH. SHOOT 8 HOLES F/</p> <p>9260' - 62', P/U SHOOT 24 HOLES F/ 9228' - 34', P/U SHOOT 8</p> <p>HOLES F/ 9186' - 88'. POOH. MIRU WEATHERFORD FRAC SVC.</p> <p>PRIME PMP'S &amp; PSI TST LINES TO 8500# (HELD). PREP TO</p> <p>FRAC</p> <p>NOTE: ALL STAGES SHOT W/ 3 3/8" EXP PERF GUNS LOADED</p> <p>W/ 23 GM CHARGES, 3 &amp; 4 SPF, 90 &amp; 120 DEG PHASING. ALL</p> <p>CBP'S ARE 4 1/2" BAKER 8K CBP'S. ALL STAGES INCLUDE</p> <p>NALCO SCALE INHIB, 3 GPT IN PAD &amp; 1/2 RAMP, 10 GPT IN</p> <p>FLUSH &amp; PRE PAD. ALL CLEAN FLUID INCLUDE NALCO BIOCID</p> <p>(new) @ .50 GPT.</p> <p>STG 1: BRK DWN PERF'S @ 4169#, EST INJ RT @ 51 BPM @</p> <p>5400#, ISIP 3287#, FG .80, TREAT STG 1 W/ 31858 SAND, TAILED</p> <p>IN W/ 5000# TLC SAND W/ SLK WTR. TOT CL FL 1016 BBLS. ISIP</p> <p>3355#, NPI 68#, FG .81</p> <p>STG 2: P/U 3 3/8" PERF GUNS &amp; 4 1/2" CBP &amp; RIH. SET CBP @</p> <p>9113', P/U SHOOT 15 HOLES F/ 9078' - 83', P/U SHOOT 9 HOLES</p> <p>F/ 9017' - 20', P/U SHOOT 9 HOLES F/ 8972' - 75', P/U SHOOT 6</p> <p>HOLES F/ 8928' - 30'. POOH. BRK DWN PERF'S @ 5085#, EST</p> <p>INJ RT @ 50.9 BPM @ 5900#, ISIP 3236#, FG .80, TREAT STG 2</p> <p>W/ 141,294# SAND TAILED IN W/ 5000# TLC SAND W/ SLK WTR.</p> <p>TOT CL FL 3818 BBLS. ISIP 2905#, NPI -331#, FG .77</p> <p>SWI. SDFN</p>					
8/20/2008	<u>SUPERVISOR:</u> WILL GLEAVE				

7:00 - 18:00	11.00	COMP	36	E	P	<p>HSM. PU 3-1/8 PERF GUNS &amp; 4-1/2 CBP. RIH, SET CBP @ 8864'. PU, SHOOT 24 HOLES FROM 8828-34'. PU, SHOOT 16 HOLES FROM 8816-20'. POOH. BREAK DOWN PERFS @ 5745#, ISIP 3256#. FG.81. EST INJ RATE OF 40 BBL/MIN @ 4600#.</p> <p>TREATED STAGE 3 W/ 73,909# SAND, TAILED IN W/ 5000# TLC SAND W/ SLK WTR. TOTAL CLEAN FLUID 1990 BBLS. ISIP 3039. FG .79. NPI -217.</p> <p>STAGE 4:. PU 3-1/8 PERF GUNS &amp; 4-1/2 CBP. RIH, SET CBP @ 8248'. PU, SHOOT 16 HOLES FROM 8214-18', PU, SHOOT 16 HOLES FROM 8146-50', PU, SHOOT 8 HOLES FROM 8020-22'. POOH. BREAK DOWN PERFS @ 6427#, ISIP 2475, FG .75. EST INJ RATE OF 51 BBL/MIN @ 5600#.. TREATED STAGE 4 W/ 87,378# SAND, TAILED IN W/ 5000# TLC SAND W/ SLK WTR. 2243 BBLS TOTAL CLEAN FLUID. ISIP 3262#. FG .84, NPI 787.</p> <p>STAGE 5:. PU 3-1/8 PERF GUNS &amp; 4-1/2 CBP. RIH, SET CBP @ 7985', PU, SHOOT 12 HOLES FROM 7951-55', PU, SHOOT 12 HOLES FROM 7916-20', PU, SHOOT 9 HOLES FROM 7890-93'. PU, SHOOT 6 HOLES FROM 7850-52'. POOH. BREAK DOWN PERFS @ 3754#, ISIP 2068, FG .70. EST INJ RATE OF 53 BBL/MIN @ 4530#. TREATED STAGE 5 W/ 167,983# SAND, TAILED IN W/ 5000# TLC SAND W/ SLK WTR. 4211 BBLS TOTAL CLEAN FLUID. ISIP 3500, FG .89, NPI 1432#.</p> <p>PU 4-1/2 CBP, RIH, SET CBP @ 7770'. POOH. RDMO CUTTERS WIRELINE. RDMO WEATHERFORD FRAC.</p> <p>PU POBS &amp; 3-7/8 ROCK &amp; TIH TO 7747'. SWI-SDFN</p>
--------------	-------	------	----	---	---	--

8/21/2008	SUPERVISOR: WILL GLEAVE					MD:
7:00 - 17:00	10.00	COMP	44	C	P	<p>HSM #4. PU SWIVEL. RU PUMP &amp; LINES. TAG KILL PLUG. BREAK CIRC. D.O. 1ST CBP @ 7,770'. 1000 # INC.</p> <p>TIH, TAG FILL @ 7,955 (30' FILL) D.O. 2ND CBP @ 7985'. 700 # INC.</p> <p>TIH, TAG FILL @ 8208' (40' FILL) D.O. 3RD CBP @ 8248'. 500 # INC.</p> <p>TIH, TAG FILL @ 8834' ( 30'FILL) D.O. 4TH CBP @ 8,864". 600 # INC.</p> <p>TIH, TAG FILL @ 9053' (60' FILL) D.O. 5TH CBP @ 9113". 500 # INC.</p> <p>TIH, TAG FILL @ 9484' (135' FILL) C.O. TO PBTD @ 9619'</p> <p>LD SWIVEL. LD 23 JTS ON TRAILER. HANG TBG OFF. ND BOPS. DROP BALL. NU WH. PUMP OFF BIT @ 3000#</p> <p>TURN OVER TO FLOW BACK CREW. RDMO TO NBU 920-20L. SDFN</p> <p>48/64 CHOKE SICP 1750 TBG PSI 100</p> <p>281 JTS IN WELL 30 ON TRAILER 311 JTS ON LOC EOT @ 8904'</p>

8/22/2008	SUPERVISOR: WILL GLEAVE					MD:
7:00 -			33	A		<p>7 AM FLBK REPORT: CP 1450#, TP 1375#, 16/64" CK, 55 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 4100 BBLS LEFT TO RECOVER: 9178</p>

8/23/2008	SUPERVISOR: WILL GLEAVE					MD:
7:00 -			33	A		<p>7 AM FLBK REPORT: CP 1150#, TP 1275#, 16/64" CK, 42 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 5195 BBLS LEFT TO RECOVER: 8083</p>

8/24/2008	SUPERVISOR: WILL GLEAVE					MD:
-----------	-------------------------	--	--	--	--	-----

Wins No.: 95182		NBU 1021-19E		API No.: 4304739006
7:00	-	33	A	7 AM FLBK REPORT: CP 800#, TP 1325#, 18/64" CK, 35 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 6170 BBLS LEFT TO RECOVER: 7108
8/25/2008	SUPERVISOR: WILL GLEAVE			MD:
7:00	-	33	A	7 AM FLBK REPORT: CP 1150#, TP 1300#, 18/64" CK, 28 BWPH, L TRACE SAND, - GAS TTL BBLS RECOVERED: 6892 BBLS LEFT TO RECOVER: 6386

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	OTHER <input type="checkbox"/>		
b. TYPE OF WORK:		NEW WELL <input checked="" type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	OTHER <input type="checkbox"/>
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP						9. API NUMBER: 4304739006	
3. ADDRESS OF OPERATOR: 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078				PHONE NUMBER: (435) 781-7024		10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2146'FNL, 879'FWL LOT 2  AT TOP PRODUCING INTERVAL REPORTED BELOW:  AT TOTAL DEPTH:						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E	
12. COUNTY UINTAH						13. STATE UTAH	

14. DATE SPUDDED: 6/22/2008	15. DATE T.D. REACHED: 8/5/2008	16. DATE COMPLETED: 8/23/2008	ABANDONED <input type="checkbox"/>	READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 5192'GL
18. TOTAL DEPTH: MD 9,680 TVD	19. PLUG BACK T.D.: MD 9,619 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD	
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CBL-CCL-GR, CCS, SD, DSN, HRI				23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
12 1/4"	9 5/8 J-55	36#		2,060		550			
7 7/8"	4 1/2 I-80	11.6#		9,680		2240			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	8.904							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) MESAVERDE	7,850	9,262			7,850 9,262	0.36	198	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) WSMVD								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
7850'-9262'	PMP 13,278 BBLS SLICK H2O & 502,422# 30/50 OTTOWA SD

29. ENCLOSED ATTACHMENTS:

- ☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY  
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: \_\_\_\_\_

30. WELL STATUS:

PROD

RECEIVED

SEP 22 2008

DIV. OF OIL, GAS & MINING

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 8/23/2008	TEST DATE: 8/29/2008	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 1,339	WATER – BBL: 312	PROD. METHOD: FLOWING
CHOKE SIZE: 18/64	TBG. PRESS. 1,009	CSG. PRESS. 1,675	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS: PROD

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
GREEN RIVER	1,113				
MAHOGANY	1,831				
WASATCH	4,415	7,013			
MESAVERDE	7,456	9,570			

## 35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 9/16/2008

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22792
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT#891008900A
PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 1021-19E
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2146' FNL, 879' FWL LOT 2		9. API NUMBER: 4304739006
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input checked="" type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


THE OPERATOR REQUESTS AUTHORIZATION TO RECOMPLETE THE SUBJECT WELL LOCATION.  
THE OPERATOR PROPOSES TO COMPLETE THE WASATCH AND THE EXISTING MESAVERDE FORMATION.  
THE OPERATOR WILL COMMINGLE THE NEWLY WASATCH AND MESAVERDE INTERVALS ALONG WITH  
THE EXISTING MESAVERDE FORMATIONS.

PLEASE REFER TO THE ATTACHED RECOMPLETION PROCEDURE.

COPY SENT TO OPERATOR


Date: 12.4.2008

Initials: KS

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 11/17/2008

(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS AND MINING

BY:  11/26/08  
(See Instructions on Reverse Side)  
# Cause 173-14

RECEIVED

NOV 24 2008

DIV. OF OIL, GAS & MINING

**Name:** NBU 1021-19E  
**Location:** SWNW-Section 19-T10S-R21E  
**Uintah County, UT**  
**Date:** **November 14, 2008**

**ELEVATIONS:**        5192' GL                      5208' KB

**TOTAL DEPTH:**        9680'                      **PBTD:** 9619'  
**SURFACE CASING:**        9 5/8", 36# J-55 ST&C @ 2032'  
**PRODUCTION CASING:**    4 1/2", 11.6#, I-80 LT&C @ 9665"  
    Marker Joint **4366'-4387'**

**TUBULAR PROPERTIES:**

	BURST (psi)	COLLAPSE (psi)	DRIFT DIA. (in.)	CAPACITIES	
				(bbl/ft)	(gal/ft)
2 3/8" 4.7# J-55 tbg	7,700	8,100	1.901"	0.00387	0.1624
4 1/2" 11.6# I-80 (See above)	7780	6350	3.875"	0.0155	0.6528
2 3/8" by 4 1/2" Annulus				0.0101	0.4227

**TOPS:**

1113' Green River  
 1831' Mahogany  
 4416' Wasatch  
 7425' Mesaverde

CBL indicates good cement bond below 3000'

**GENERAL:**

- A minimum of **25** tanks (cleaned lined 500 bbl) of recycled water will be required. Note: Use biocide in tanks and the water needs to be at least 45°F at pump time.
- All perforation depths are from Halliburtons Induction-Density-Neutron log dated 08/06/2008.
- **9** fracturing stages required for coverage.
- Procedure calls for 9 CBP's (**8000** psi) and **1 flow through plug** (8000 psi).
- Calculate open perforations after each breakdown. If less than 60% of the perforations appear to be open, ball out with 15% HCl.
- Put scale inhibitor 3 gals/1000 gals (in pad and 1/2 the ramp) and 10 gals/1000 gals in all flushes except the final stage. Remember to pre-load the casing with scale inhibitor for the very first stage with 10 gpt.
- 30/50 mesh Ottawa sand, **Slickwater frac.**
- Maximum surface pressure **6200** psi.
- Flush volumes are the sum of slick water and acid used during displacement (include scale inhibitor as mentioned above). **DO NOT OVERDISPLACE.** Stage acid and scale inhibitor if necessary to cover the next perforated interval.
- Service companies need to provide surface/production annulus pop-offs to be set for 1500 psi for each frac.

- Pump resin coated sand last 5,000# of all frac stages
- Tubing Currently Landed @~8904'
- Originally completed on 8/21/08

**Existing Perforations:**

Stage	Zones	Perforations		SPF	Holes
		Top, ft	Bottom, ft		
1	MESAVERDE	9186	9188	4	8
	MESAVERDE	9228	9234	4	24
	MESAVERDE	9260	9262	4	8
	# of Perfs/stage				40
2	MESAVERDE	8928	8930	3	6
	MESAVERDE	8972	8975	3	9
	MESAVERDE	9017	9020	3	9
	MESAVERDE	9078	9083	3	15
	# of Perfs/stage				39
3	MESAVERDE	8816	8820	4	16
	MESAVERDE	8828	8834	4	24
	# of Perfs/stage				40
4	MESAVERDE	8020	8022	4	8
	MESAVERDE	8146	8150	4	16
	MESAVERDE	8214	8218	4	16
	# of Perfs/stage				40
5	MESAVERDE	7850	7852	3	6
	MESAVERDE	7890	7893	3	9
	MESAVERDE	7916	7920	3	12
	MESAVERDE	7951	7955	3	12
	# of Perfs/stage				39

**PROCEDURE:**

1. MIRU. Control well with recycled water and biocide as required. ND WH, NU BOP's and test.
2. If the tubing is below the proposed CBP depth, TOO H with 2-3/8", 4.7#, N-80 tubing (currently landed at ~8904'). Visually inspect for scale and consider replacing if needed. If the tubing is above the proposed CBP depth, RIH with tubing and tag for fill before TOO H.
3. If tb g looks ok consider running a gauge ring to 7836' (50' below proposed CBP). Otherwise P/U a mill and C/O to 7836' (50' below proposed CBP).
4. Set 8000 psi Flow Through Plug at ~ 7786'. Pressure test BOP and casing to 6000 psi. .
5. Perf the following with 3-3/8" gun, 23 gm, 0.36"hole:

Zone	From	To	spf	# of shots
MESAVERDE	7742	7756	3	42

6. Breakdown perfs and establish injection rate (include scale inhibitor in fluid). Spot 250 gals of 15% HCL and let soak 5-10 min. Fracture as outlined in Stage 1 on attached listing. Under-displace to ~7692' and trickle 250gal 15%HCL w/ scale inhibitor in flush. Note: Stage is pumped at a reduced rate.

7. Set 8000 psi CBP at ~7512'. Perf the following 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
MESAVERDE	7468	7482	3	42

8. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 2 on attached listing. Under-displace to ~7424' and trickle 250gal 15%HCL w/ scale inhibitor in flush. Note: Stage has tight spacing and is pumped at a reduced rate.

9. Set 8000 psi CBP at ~7414'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	7280	7282	3	6
WASATCH	7298	7300	3	6
WASATCH	7330	7334	3	12
WASATCH	7380	7384	4	16

10. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 3 on attached listing. Under-displace to ~7230' trickle 250gal 15%HCL w/ scale inhibitor in flush.

11. Set 8000 psi CBP at ~7143'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	7006	7014	3	24
WASATCH	7068	7071	3	9
WASATCH	7110	7113	3	9

12. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 4 on attached listing. Under-displace to ~6956' and trickle 250gal 15%HCL w/ scale inhibitor in flush. Note: Stage has tight spacing.

13. Set 8000 psi CBP at ~6942'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6752	6756	3	12
WASATCH	6818	6820	3	6
WASATCH	6854	6858	4	16
WASATCH	6910	6912	4	8

14. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 5 on attached listing. Under-displace to ~6730' and trickle 250gal 15%HCL w/ scale inhibitor in flush. Note: Stage has tight spacing.

15. Set 8000 psi CBP at ~6720'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6552	6558	3	18

WASATCH 6682 6690 3 24

16. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 6 on attached listing. Under-displace to ~6502' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

17. Set 8000 psi CBP at ~6440'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6238	6240	3	6
WASATCH	6249	6251	3	6
WASATCH	6266	6268	3	6
WASATCH	6282	6284	3	6
WASATCH	6406	6410	4	16

18. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 7 on attached listing. Under-displace to ~6188' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

19. Set 8000 psi CBP at ~6113'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	5946	5948	3	6
WASATCH	5972	5974	3	6
WASATCH	6000	6003	3	9
WASATCH	6016	6018	4	8
WASATCH	6080	6083	4	12

20. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 8 on attached listing. Under-displace to ~5896' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

21. Set 8000 psi CBP at ~5636'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	5516	5522	3	18
WASATCH	5582	5586	3	12
WASATCH	5602	5606	3	12

22. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 9 on attached listing. Under-displace to ~5466' and flush only with recycled water.

23. Set 8000 psi CBP at ~5466'.

24. TIH with 3 7/8" bit, pump off sub, SN and tubing.

25. Drill plugs and clean out to flow through plug at 7786' (do not drill out). Open sleeve and DO NOT PUMP OFF SUB and land tubing at ±7438' unless indicated otherwise by the well's behavior. This well will be commingled at this time. As well dictates, come back to location and drill flow through plug, clean out to 9619', and land tubing at +/- 8900'.

26. RDMO

**For design questions, please call**

**David Cocciolone, Denver, CO**  
**(832)-453-2043 (Cell)**  
**(720)-929-6716 (Office)**

**For field implementation questions, please call**  
**Robert Miller, Vernal, UT**  
**(435)-781-7041 (Office)**

NOTES:

Expected incremental IP of 450 MCFD. Well is currently producing 455 MCFD. Expected IP of 905 MCFD.

Recompleted similar to NBU 1021-19D and 19C, though this recomplete is utilizing slickwater. Going after sands not typically thought of as pay (shalier intervals).

**NBU 1021-19E Recomplete  
Perforation and CBP Summary**

Stage	Zones	Perforations		SPF	Holes	Fracture Coverage		
		Top, ft	Bottom, ft					
1	MESAVERDE	7742	7756	3	42	7603	to	7604
	MESAVERDE		No Perfs			7620	to	7620
	MESAVERDE		No Perfs			7626	to	7637
	MESAVERDE		No Perfs			7651	to	7654
	MESAVERDE		No Perfs			7658	to	7663
	MESAVERDE		No Perfs			7666	to	7669
	MESAVERDE		No Perfs			7684	to	7691
	MESAVERDE		No Perfs			7742	to	7757
	# of Perfs/stage				42	CBP DEPTH	7,512	
2	MESAVERDE	7468	7482	3	42	7459	to	7464
	MESAVERDE		No Perfs			7468	to	7475
	MESAVERDE		No Perfs			7476	to	7481
	MESAVERDE		No Perfs			7483	to	7486
	MESAVERDE		No Perfs			7488	to	7490
	MESAVERDE		No Perfs			7500	to	7502
	MESAVERDE		No Perfs			7507	to	7507
	MESAVERDE		No Perfs			7515	to	7515
	MESAVERDE		No Perfs			7521	to	7523
	MESAVERDE		No Perfs			7524	to	7525
	# of Perfs/stage				42	CBP DEPTH	7,414	
3	WASATCH	7280	7282	3	6	7206	to	7208
	WASATCH	7298	7300	3	6	7237	to	7237
	WASATCH	7330	7334	3	12	7250	to	7250
	WASATCH	7380	7384	4	16	7279	to	7280
	WASATCH		No Perfs			7291	to	7291
	WASATCH		No Perfs			7326	to	7327
	WASATCH		No Perfs			7372	to	7372
	WASATCH		No Perfs			7381	to	7388
	# of Perfs/stage				40	CBP DEPTH	7,143	
4	WASATCH	7006	7014	3	24	6982	to	6982
	WASATCH	7068	7071	3	9	6995	to	6999
	WASATCH	7110	7113	3	9	7010	to	7013
	WASATCH		No Perfs			7039	to	7039
	WASATCH		No Perfs			7069	to	7070
	WASATCH		No Perfs			7074	to	7074
	WASATCH		No Perfs			7079	to	7080
	WASATCH		No Perfs			7111	to	7114
	WASATCH		No Perfs			7147	to	7148
	# of Perfs/stage				42	CBP DEPTH	6,942	
5	WASATCH	6752	6756	3	12	6716	to	6716
	WASATCH	6818	6920	3	6	6814	to	6814
	WASATCH	6854	6858	4	16	6851	to	6851
	WASATCH	6910	6912	4	8	6855	to	6855
	WASATCH		No Perfs			6877	to	6878
	WASATCH		No Perfs			6906	to	6907
	WASATCH		No Perfs			6908	to	6909
	WASATCH		No Perfs			6938	to	6950
	# of Perfs/stage				42	CBP DEPTH	6,720	
6	WASATCH	6552	6558	3	18	6472	to	6472
	WASATCH	6682	6690	3	24	6502	to	6502
	WASATCH		No Perfs			6546	to	6547
	WASATCH		No Perfs			6552	to	6560
	WASATCH		No Perfs			6561	to	6561
	WASATCH		No Perfs			6630	to	6630
	WASATCH		No Perfs			6645	to	6646
	WASATCH		No Perfs			6687	to	6692
	# of Perfs/stage				42	CBP DEPTH	6,440	
7	WASATCH	6238	6240	3	6	6150	to	6150
	WASATCH	6249	6251	3	6	6261	to	6261
	WASATCH	6266	6268	3	6	6266	to	6269
	WASATCH	6282	6284	3	6	6284	to	6284
	WASATCH	6406	6410	4	16	6403	to	6404
	WASATCH		No Perfs			6408	to	6406
	WASATCH		No Perfs			6408	to	6408
	WASATCH		No Perfs			6410	to	6410
	WASATCH		No Perfs			6452	to	6460
	# of Perfs/stage				40	CBP DEPTH	6,113	
8	WASATCH	5946	5948	3	6	5825	to	5825
	WASATCH	5972	5974	3	6	5872	to	5872
	WASATCH	6000	6003	3	9	5984	to	5984
	WASATCH	6016	6018	4	8	6000	to	6004
	WASATCH	6080	6083	4	12	6008	to	6008
	WASATCH		No Perfs			6035	to	6035
	WASATCH		No Perfs			6107	to	6115
	# of Perfs/stage				41	CBP DEPTH	5,636	
9	WASATCH	5516	5522	3	18	5508	to	5525
	WASATCH	5582	5588	3	12	5583	to	5588
	WASATCH	5602	5606	3	12	5589	to	5594
	WASATCH		No Perfs			5598	to	5608
	# of Perfs/stage				42	CBP DEPTH	5,466	
Totals					373			



Recurring Schedule  
NBU 1021-19E Recomplete  
Slickwater Frac

Stage	Zone	Foot of Pay	Perfs Top, ft. Bot. ft.	SPF	Holes	BPM	Rate	Fluid Type	Initial PPG	Final PPG	Fluid	Volume BBLs	Cum Vol BBLs	Fluid % of frac	Sand % of frac	Sand lbs	Cum. Sand lbs	Footage from CHP to Flush	Scale Inhib.
1	MESAVERDE	0	7742 7750	3	42	Varied	Pump-in test	ISDP and 5 min ISDP			Slickwater	0	0						49
	MESAVERDE	0	No Perfs				ISDP and 5 min ISDP				Slickwater	362	362	15.0%	0.0%	0	0		49
	MESAVERDE	11	No Perfs				Slickwater Pad				Slickwater	883	1,045	20.3%	16.0%	17,930	17,930		43
	MESAVERDE	3	No Perfs				Slickwater Ramp		0.25	1	Slickwater	0	1,045	0.0%	0.0%	0	17,930		0
	MESAVERDE	6	No Perfs				SW Swaps		0	15	Slickwater	183	1,728	20.3%	51.5%	35,859	53,789		43
	MESAVERDE	3	No Perfs				Slickwater Ramp		0	0	Slickwater	125	1,853	0.0%	0.0%	0	53,789		0
	MESAVERDE	7	No Perfs				SW Swaps		0	0	Slickwater	71	1,924	0.0%	0.0%	3,000	56,789		0
	MESAVERDE	15	No Perfs				Slickwater Ramp		0.5	15	Slickwater	183	2,536	20.3%	46.9%	50,203	106,992		43
	MESAVERDE						Flush (4-1/2")		1.5	2	Slickwater	120	2,655				108,092		229
							ISDP and 5 min ISDP												
							Sand laden Volume									2,260	2,379	lbs sand/ft	
							Flush depth									7692	CBP depth	7,512	
2	MESAVERDE	0	7402 7402	3	42	Varied	Pump-in test	ISDP and 5 min ISDP			Slickwater	0	0						27
	MESAVERDE	7	No Perfs				ISDP and 5 min ISDP				Slickwater	217	217	15.0%	0.0%	0	0		26
	MESAVERDE	6	No Perfs				Slickwater Pad		0.25	1	Slickwater	410	627	20.3%	17.2%	10,758	10,758		0
	MESAVERDE	2	No Perfs				Slickwater Ramp		0	0	Slickwater	0	627	0.0%	0.0%	0	10,758		26
	MESAVERDE	0	No Perfs				SW Swaps		0	15	Slickwater	410	1,037	20.3%	34.6%	21,516	32,273		0
	MESAVERDE	0	No Perfs				Slickwater Ramp		0	0	Slickwater	0	1,037	0.0%	0.0%	0	32,273		0
	MESAVERDE	0	No Perfs				SW Swaps		0	0	Slickwater	0	1,037	0.0%	0.0%	0	32,273		0
	MESAVERDE	0	No Perfs				Slickwater Ramp		0.5	15	Slickwater	410	1,448	20.3%	48.3%	30,122	62,395		0
	MESAVERDE	2	No Perfs				Flush (4-1/2")		1.5	2	Slickwater	115	1,562				62,395		127
							ISDP and 5 min ISDP												
							Sand laden Volume									2,250	2,311	lbs sand/ft	
							Flush depth									7424	CBP depth	7,414	
3	WASATCH	0	7290 7300	3	42	Varied	Pump-in test	ISDP and 5 min ISDP			Slickwater	0	0						10
	WASATCH	0	7330 7334	3	12	0	ISDP and 5 min ISDP				Slickwater	70	70	15.0%	0.0%	0	0		0
	WASATCH	1	7360 7364	4	18	0	Slickwater Pad		0.25	1	Slickwater	148	227	20.3%	17.2%	3,806	3,806		0
	WASATCH	0	No Perfs				Slickwater Ramp		0	0	Slickwater	0	227	0.0%	0.0%	0	3,806		9
	WASATCH	0	No Perfs				SW Swaps		0	15	Slickwater	148	375	20.3%	34.5%	7,792	11,608		0
	WASATCH	0	No Perfs				Slickwater Ramp		0	0	Slickwater	0	375	0.0%	0.0%	0	11,608		0
	WASATCH	0	No Perfs				SW Swaps		0	0	Slickwater	0	375	0.0%	0.0%	0	11,608		0
	WASATCH	7	No Perfs				Slickwater Ramp		0.5	15	Slickwater	148	521	20.3%	48.3%	10,908	22,506		0
	WASATCH						Flush (4-1/2")		1.5	2	Slickwater	112	636				22,506		75
							ISDP and 5 min ISDP												
							Sand laden Volume									2,000	2,054	lbs sand/ft	
							Flush depth									7230	CBP depth	7,143	
4	WASATCH	0	7005 7014	3	42	Varied	Pump-in test	ISDP and 5 min ISDP			Slickwater	0	0						12
	WASATCH	4	7069 7071	3	9	0	ISDP and 5 min ISDP				Slickwater	93	93	15.0%	0.0%	0	0		11
	WASATCH	0	7110 7113	3	9	0	Slickwater Pad		0.25	1	Slickwater	175	268	20.3%	17.2%	4,604	4,604		0
	WASATCH	0	No Perfs				Slickwater Ramp		0	0	Slickwater	0	268	0.0%	0.0%	0	4,604		11
	WASATCH	0	No Perfs				SW Swaps		0	15	Slickwater	175	444	20.3%	34.6%	9,208	13,813		0
	WASATCH	0	No Perfs				Slickwater Ramp		0.5	15	Slickwater	175	619	20.3%	48.3%	12,892	26,704		0
	WASATCH	3	No Perfs				Flush (4-1/2")		1.5	2	Slickwater	108	727				26,704		75
							ISDP and 5 min ISDP												
							Sand laden Volume									2,000	2,054	lbs sand/ft	
							Flush depth									6956	CBP depth	6,942	
5	WASATCH	0	6752 6756	3	42	Varied	Pump-in test	ISDP and 5 min ISDP			Slickwater	0	0						14
	WASATCH	0	6818 6820	3	6	0	ISDP and 5 min ISDP				Slickwater	107	107	15.0%	0.0%	0	0		13
	WASATCH	0	6854 6854	4	18	0	Slickwater Pad		0.25	1	Slickwater	202	310	20.3%	17.2%	5,313	5,313		0
	WASATCH	1	6910 6912	4	0	0	Slickwater Ramp		0	0	Slickwater	0	310	0.0%	0.0%	0	5,313		13
	WASATCH	1	No Perfs				SW Swaps		0	15	Slickwater	202	512	20.3%	34.6%	10,627	15,938		0
	WASATCH	1	No Perfs				Slickwater Ramp		0	0	Slickwater	0	512	0.0%	0.0%	0	15,938		0
	WASATCH	1	No Perfs				SW Swaps		0	0	Slickwater	0	512	0.0%	0.0%	0	15,938		0
	WASATCH	1	No Perfs				Slickwater Ramp		0.5	15	Slickwater	202	714	20.3%	48.3%	14,875	30,813		0
	WASATCH	1	No Perfs				Flush (4-1/2")		1.5	2	Slickwater	105	819				30,813		25
							ISDP and 5 min ISDP												
							Sand laden Volume									2,000	2,054	lbs sand/ft	
							Flush depth									6730	CBP depth	6,720	
6	WASATCH	0	6552 6552	3	42	Varied	Pump-in test	ISDP and 5 min ISDP			Slickwater	0	0						15
	WASATCH	0	6602 6600	3	24	0	ISDP and 5 min ISDP				Slickwater	121	121	15.0%	0.0%	0	0		14
	WASATCH	0	No Perfs				Slickwater Pad		0.25	1	Slickwater	228	348	20.3%	17.2%	5,977	5,977		0
	WASATCH	0	No Perfs				Slickwater Ramp		0	0	Slickwater	0	348	0.0%	0.0%	0	5,977		14
	WASATCH	0	No Perfs				SW Swaps		0	15	Slickwater	228	576	20.3%	34.6%	11,953	17,930		0
	WASATCH	0	No Perfs				Slickwater Ramp		0	0	Slickwater	0	576	0.0%	0.0%	0	17,930		0
	WASATCH	0	No Perfs				SW Swaps		0	0	Slickwater	0	576	0.0%	0.0%	0	17,930		0
	WASATCH	5	No Perfs				Slickwater Ramp		0.5	15	Slickwater	228	804	20.3%	48.3%	16,734	34,664		0
	WASATCH						Flush (4-1/2")		1.5	2	Slickwater	101	905				34,664		20
							ISDP and 5 min ISDP												
							Sand laden Volume									2,260	2,311	lbs sand/ft	
							Flush depth									6502	CBP depth	6,440	
7	WASATCH	0	6238 6240	3	42	Varied	Pump-in test	ISDP and 5 min ISDP			Slickwater	0	0						12
	WASATCH	0	6249 6251	3	6	0	ISDP and 5 min ISDP				Slickwater	98	98	15.0%	0.0%	0	0		11
	WASATCH	3	6268 6268	3	12	0	Slickwater Pad		0.25	1	Slickwater	182	279	20.3%	17.2%	4,781	4,781		0
	WASATCH	0	6272 6274	3	6	0	Slickwater Ramp		0	0	Slickwater	0	279	0.0%	0.0%	0	4,781		11
	WASATCH	1	6406 6410	4	15	0	SW Swaps		0	15	Slickwater	182	461	20.3%	34.6%	9,563	14,344		0
	WASATCH	0	No Perfs				Slickwater Ramp		0	0	Slickwater	0	461	0.0%	0.0%	0	14,344		0
	WASATCH	0	No Perfs				SW Swaps		0	0	Slickwater	0	461	0.0%	0.0%	0	14,344		0
	WASATCH	0	No Perfs				Slickwater Ramp		0.5	15	Slickwater	182	643	20.3%	48.3%	13,388	27,731		0
	WASATCH	1	No Perfs				Flush (4-1/2")		1.5	2	Slickwater	95	739				27,731		75
							ISDP and 5 min ISDP												
							Sand laden Volume									2,260	2,311	lbs sand/ft	
							Flush depth									6199	CBP depth	6,113	
8	WASATCH	0	6048 6048	3	42	Varied	Pump-in test	ISDP and 5 min ISDP			Slickwater	0	0						11
	WASATCH	0	6072 6074	3	6	0	ISDP and 5 min ISDP				Slickwater	85	85	15.0%	0.0%	0	0		10
	WASATCH	0	6000 6003	3	9	0	Slickwater Pad		0.25	1	Slickwater	162	248	20.3%	17.2%	4,250	4,250		0
	WASATCH	0	6000 6003	4	12	0	Slickwater Ramp		0	0	Slickwater	0	248	0.0%	0.0%	0	4,250		10
	WASATCH	0	6000 6003	3	9	0	SW Swaps		0	15	Slickwater	162	410	20.3%	34.6%	8,500	12,750		0
	WASATCH	0	No Perfs				Slickwater Ramp		0	0	Slickwater	0	410	0.0%	0.0%	0	12,750		0
	WASATCH	0	No Perfs				SW Swaps		0	0	Slickwater	0	410	0.0%	0.0%	0	12,750		0
	WASATCH	0	No Perfs				Slickwater Ramp		0.5	15	Slickwater	162	571	20.3%	48.3%	11,900	24,650		0
	WASATCH	1	No Perfs				Flush (4-1/2")		1.5	2	Slickwater	92	663				24,650		68
							ISDP and 5 min ISDP												
							Sand laden Volume									4,800	4,930	lbs sand/ft	
							Flush depth									5895	CBP depth	5,636	

[illegible]

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22792
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2146'FNL, 879'FWL LOT 2		8. WELL NAME and NUMBER: NBU 1021-19E
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 19 10S 21E		9. API NUMBER: 4304739006
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input checked="" type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR HAS PERFORMED A RECOMPLETION ON THE SUBJECT WELL LOCATION. THE OPERATOR HAS COMPLETED THE WASATCH AND MESAVERDE FORMATIONS. THE OPERATOR HAS COMMINGLED THE NEWLY WASATCH AND MESAVERDE INTERVALS, ALONG WITH THE EXISTING MESAVERDE FORMATION. THE OPERATOR HAS PLACED THE SUBJECT WELL LOCATION ON PRODUCTION ON 01/09/2009 AT 1100 HRS.

PLEASE REFER TO THE ATTACHED RECOMPLETION CHRONOLOGICAL WELL HISTORY.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 1/13/2009

(This space for State use only)

RECEIVED  
JAN 20 2009

DIV. OF OIL, GAS & MINING

<b>Wins No.: 95182</b>		<b>NBU 1021-19E</b>		<b>API No.: 4304739006</b>	
<b>EVENT INFORMATION:</b>		EVENT ACTIVITY: RECOMPLETION		START DATE: 12/29/2008	
		OBJECTIVE: DEVELOPMENT		END DATE: 1/7/2009	
		OBJECTIVE 2: RECOMPLETE		DATE WELL STARTED PROD.:	
		REASON: MV, WAS		Event End Status: COMPLETE	
<b>RIG OPERATIONS:</b>		Begin Mobilization	Rig On Location	Rig Charges	Rig Operation Start
					Finish Drilling
					Rig Release
					Rig Off Location
GWS 1 / 1		12/29/2008			01/07/2009
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode
					P/U
					Operation
12/29/2008	<u>SUPERVISOR:</u> DAVID DANIELS <span style="float:right"><u>MD:</u></span>				
	7:00 - 7:30	0.50	COMP	48	P HSM.
	7:30 - 18:00	10.50	COMP	31	I P ROAD RIG F/ BITTER CREEK 1122-4G, T/ NBU 1021-19E. MIRU RIG SPOT EQUIP. BLOW WELL DOWN T/ PROD TANK. 500# SICP. FTP 120#. BLOW WELL T/ 0#. RIG PUMP T/ TBG. PUMP 30 BBLS 2% KCL T/ CONTROL WELL. NDWH, NU BOP. RU TBG EQUIP & RIG FLOOR. RIG PUMP T/ CSG PUMP 120 BBLS 2% KCL T/ CONTROL WELL. UNLAND TBG, LD 4 1/16 TBG HNGR. POOH SB 226 JTS, LD 55 JTS 2 3/8, L-80 TBG. ND BOP, NU FRAC VALVES. MIRU CUTTER W.L.. PU 4 1/2, 8K FLTH CBP. RIH SET @ 7797'. POOH. RDMO CUTTERS W.L.. MIRU B&C QUICK TEST. RIG PUMP T/ CSG. FILL CSG W/ 120 BBLS 2% KCL. PSI T/ 2000#. CONTINUE PSI T/ 6200# W/ B&C QUICK TEST. GOOD TEST. BLEED OFF PSI T/ PIT. WINTERIZE WH. SWI. SDFN.
12/30/2008	<u>SUPERVISOR:</u> DAVID DANIELS <span style="float:right"><u>MD:</u></span>				
	7:00 - 15:00	8.00	COMP	46	F P STDBY. WAIT ON WEATHERFORD FRAC SERV.
12/31/2008	<u>SUPERVISOR:</u> DAVID DANIELS <span style="float:right"><u>MD:</u></span>				
	7:00 - 15:00	8.00	COMP	46	E P STDBY. WAIT ON WEATHERFORD FRAC SERV.
1/2/2009	<u>SUPERVISOR:</u> DAVID DANIELS <span style="float:right"><u>MD:</u></span>				
	7:00 - 15:00	8.00	COMP	46	P STDBY. WAIT ON WEATHERFORD FRAC SERV
1/5/2009	<u>SUPERVISOR:</u> DAVID DANIELS <span style="float:right"><u>MD:</u></span>				
	7:00 - 7:30	0.50	COMP	48	P HSM
	7:30 - 17:30	10.00	COMP	36	B P MIRU WEATHERFORD FRAC SERV & CUTTERS W.L.. OPEN WELL 0#. STG 1) PU 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH PERF F/ 7742'-56', 3 SPF, 42 HOLES. POOH. X-OVER FOR FRAC CREW. OPEN WELL 0#. BEG PUMP BRK @ 4428# @ 3.1 BPM. SD ISIP 2266#, FG .74. BEG FRAC , PUMP 102,020# 30/50 WHITE & TAIL IN W/ 5000# 20/40 TLC. SD ISIP 3138#, FG.85. X-OVER FOR W.L..  STG 2) PU 4 1/2, 8K BAKER CBP & 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7512', P/U PERF F/ 7468'-82', 3 SPF, 42 HOLES. POOH, X-OVER FOR FRAC CREW. OPEN WELL 770#. BEG PUMP BRK @ 4536# @ 2.8 BPM. SD ISIP 2454#, FG .77. BEG FRAC PUMP 57,379# 30/50 OWATTA & TAIL IN W/ 5,000# TLC 20/40. SD ISIP 2990#, FG .84. X-OVER FOR W.L..  STG 3) PU 4 1/2, 8K BAKER CBP & 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 & 90 DEG PHASING. RIH SET CBP @ 7414', P/U PERF F/ 7280'-82', 3 SPF, 6 HOLES. 7298'-00', 3 SPF, 6 HOLES. 7330'-34', 3 SPF, 12 HOLES. 7380'-84', 4 SPF, 16 HOLES. POOH. X-OVER FOR FRAC CREW. OPEN WELL 1300#. BEG PUMP BRK @ 4595#, @ 4.9 BPM. SD ISIP 3263#, FG .89. BEG FRAC PUMP 17,717# 30/50 WHITE, TAIL IN W/ 5,000# TLC 20/40. SD ISIP 3820#, FG .96. X-OVER FOR W.L..  STG 4) PU 4 1/2, 8K BAKER CBP & 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. RIH SET CBP @ 7143', P/U PERF F/ 7006'-14', 3 SPF, 24 HOLES. 7068'-71', 3 SPF, 9 HOLES. 7110'-13', 3 SPF, 9 HOLES. POOH. X-OVER FOR FRAC CREW. OPEN WELL 160#. BEG PUMP BRK @ 2439# @ 3.2 BPM. SD ISIP 1544#, FG .66. BEG FRAC PUMP 21,671# 30/50 WHITE, TAIL IN W/ 5,000# TLC 20/40. SD ISIP 3162#, FG .89. SWI. WINTERIZE WELL HEAD. SDFN.

1/6/2009 SUPERVISOR: DAVID DANIELS

MD:

7:00 - 7:30 0.50 COMP 48 P HSM  
 7:30 - 18:00 10.50 COMP 36 B P OPEN WELL 1765#.  
 STG 5) PU 4 1/2, 8K BAKER CBP & 3 3/8 EXP GUN, 23 GM, .36  
 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 6928'. P/U PERF  
 F/  
 6752'-56', 3 SPF, 12 HOLES.  
 6818'-20', 3 SPF, 6 HOLES.  
 6854'-58', 4 SPF, 16 HOLES.  
 6910'-12', 4 SPF, 8 HOLES. POOH. X-OVER FOR FRAC CREW.  
 OPEN WELL 231#. BEG PUMP BRK @ 3569' @ 2.9 BPM. SD ISIP  
 2380#, FG .79. BEG FRAC PUMP 25,834# 30/50 WHITE, TAIL IN  
 W/ 5,000# TLC 20/40. SD ISIP 2883#, FG .87. X-OVER FOR W.L..

STG 6) PU 4 1/2, 8K BAKER CBP & 3 3/8 EXP GUN, 23 GM, .36  
 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 6708'. P/U PERF  
 F/  
 6552'-58', 3 SPF, 18 HOLES.  
 6682'-90', 3 SPF, 24 HOLES. POOH. X-OVER FOR FRAC CREW.  
 OPEN WELL 200#. BEG PUMP BRK @ 3071# @ 2.9 BPM. SD ISIP  
 1862#, FG .73. BEG FRAC PUMP 29,765# 30/50 WHITE, TAIL IN W/  
 5,000# TLC 20/40. SD ISIP 2693#, FG .85. X-OVER FOR W.L..

STG 7) PU 4 1/2, 8K BAKER CBP & 3 3/8 EXP GUN, 23 GM, .36  
 HOLE SIZE. 120 & 90 DEG PHASING. RIH SET CBP @ 6428', P/U  
 PERF F/  
 6238'-40', 3 SPF, 6 HOLES.  
 6249'-51', 3 SPF, 6 HOLES.  
 6266'-68', 3 SPF, 6 HOLES.  
 6282'-84', 3 SPF, 6 HOLES.  
 6406'-10', 4 SPF, 16 HOLES. POOH. X-OVER FOR FRAC CREW.  
 OPEN WELL 800#. BEG PUMP BRK @ 3123# @ 3.1 BPM. SD ISIP  
 2227#, FG .80. BEG FRAC PUMP PAD & 5335# SAND LOST  
 SUCKTION T/ CAS, HAD T/ SD FOR 4 MIN. FIXED PROBLEM,  
 CONTINUE FRAC. PUMP 23,289# 30/50 WHITE, TAIL IN W/ 5,000#  
 TLC 20/40. SD ISIP 2278#, FG .80. X-OVER FOR W.L..

STG 8) PU 4 1/2, 8K BAKER CBP & 3 3/8 EXP GUN, 23 GM, .36  
 HOLE SIZE. 120 & 90 DEG PHASING. RIH SET CBP @ 6113', P/U  
 PERF F/  
 5946'-48', 3 SPF, 6 HOLES.  
 5972'-74', 3 SPF, 6 HOLES.  
 6000'-03', 3 SPF, 9 HOLES.  
 6016'-18', 4 SPF, 8 HOLES.  
 6080'-83', 4 SPF, 12 HOLES. POOH. X-OVER FOR FRAC CREW.  
 OPEN WELL 400#. BEG PUMP BRK @ 2360# @ 3.3 BPM. SD ISIP  
 1876#, FG .76. BEG FRAC PUMP 19,718# 30/50 WHITE TAIL IN W/  
 5,000# TLC 20/40. SD ISIP 2270#, FG .82. X-OVER FOR W.L..

STG 9) PU 4 1/2, 8K CBP & 3 3/8 EXP GUN, 23 GM CHARGE, .36  
 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 5622' P/U PERF  
 F/  
 5516'-22', 3 SPF, 18 HOLES.  
 5582'-86', 3 SPF, 12 HOLES.  
 5602'-06', 3 SPF, 12 HOLES. POOH. X-OVER T/ FRAC CREW.  
 OPEN WELL 0#. BEG PUMP BRK @ 1788# @ 2.9 BPM. SD ISIP  
 1047#, FG .63. BEG FRAC. PUMP PAD STARTED SAND PUMP #  
 10 BLEW ANTI FREEZE HOSE. SHUT IN PUMP #10. CONT  
 FRACING PUMPED 32,000# 30/50, HAD T/ SD. PUMP #4  
 CRACKED 3" LINE OFF FLUID END. UNHOOK PUMP F/ 4" LINE.  
 SHUT DOWN FOR A TOTAL OF 8 MIN. CONT FRAC AS PER  
 PROCEDURE. PUMPED 97,516# 30/50 WHITE TAIL IN W/ 5,000#  
 TLC 20/40. SD ISIP 2429#, FG .88. X-OVER FOR W.L.. PU 4 1/2, 8K  
 BAKER CBP. RIH SET CBP @ 5471'. POOH. RDMO CUTTERS W.L.  
 & WEATHERFORD FRAC SERV. BLEED OFF WELL PSI. ND FRAC  
 VALVES. NUBOP. RU RIG FLOOR & TBG EQUIP. SWI, SDFN.

(STG 1 AND 9 PUMPED 125 BBL SWEEP W/ 71 BBL .50 T/ 1.5#  
 RAMP.)

1/7/2009 SUPERVISOR: DAVID DANIELS

MD:

7:00 - 7:30 0.50 COMP 48 P HSM

Wins No.: 95182		NBU 1021-19E				API No.: 4304739006	
7:30	- 18:00	10.50	COMP	44	C	P	OPEN WELL 0#. PU 3 7/8 BIT + X-DART + POBS + XN-NIPPLE 1.875. RIH W/ TBG. TAG FILL @ 5466'. RU DRL EQUIP & BRK CONV CIRC. CBP 1)TAG FILL @ 5466'=5' FILL. C/O SAND. DRL OUT CBP @ 5471' IN 8 MIN, 0# INCR. CONT RIH.  CBP 2)TAG FILL @ 5602'= 20' FILL. C/O SAND. DRL OUT CBP @ 5622' IN 8 MIN. 600# INCR. CONT RIH.  CBP 3)TAG FILL @ 6103'= 10' FILL. C/O SAND. DRL OUT CBP @ 6113' IN 35 MIN. 200# INCR. CONT RIH.  CBP 4)TAG FILL @ 6418'= 10' FILL. C/O SAND. DRL OUT CBP @ 5428' IN 7 MIN. 300# INCR. CONT RIH.  CBP 5)TAG FILL @ 6678'= 30' FILL. C/O SAND. DRL OUT CBP @ 6708' IN 6 MIN. 200# INCR. CONT RIH.  CBP 6)TAG FILL @ 6898'= 30' FILL. C/O SAND. DRL OUT CBP @ 6928' IN 7 MIN. 100# INCR. CONT RIH.  CBP 7)TAG FILL @ 7100'=43' FILL. C/O SAND. DRL OUT CBP @ 7143' IN 5 MIN. 100# INCR. CONT RIH.  CBP 8)TAG FILL @ 7384'= 30' FILL. C/O SAND. DRL OUT CBP @ 7414' IN 7 MIN. CONT RIH.  CBP 9)TAG FILL @ 7494'= 25' FILL. C/O SAND. DRL OUT CBP @ 7515' IN 8 MIN. 300# INCR. CONT RIH, TAG FILL 7767'. C/O 30' T/ THE TOP OF FLHT CBP @ 7797'. CIRC WELL W/ 40 BBLS 2% KCL. RD DRL EQUIP. P/U LD EXCESS TBG. PU 4 1/16 TBG HNGR & LAND TBG W/  KB 16.00 4 1/16 TBG HNGR .83 234 JTS L-80 TBG 7398.88 SLIDE OPEN BITSUB 3.13  EOT @ 7418.84  NDBOP, NU WH. DROP BALL. PUMP BIT OPEN W/ 1600#. OPEN WELL T/ PIT. TURN WELL OVER T/ FBC. SICP 550#, FTP 25# ON 64/64 CHOKE. RACK OUT EQUIP. SDFN.
1/8/2009	SUPERVISOR: WENDALL MYRICK						MD:
7:00	-	33	A				7 AM FLBK REPORT: CP 1350#, TP 150#, OPEN/64" CK, 75 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 2445 BBLS LEFT TO RECOVER: 8822
1/9/2009	SUPERVISOR: WENDALL MYRICK						MD:
7:00	-	33	A				7 AM FLBK REPORT: CP 1775#, TP 875#, 30/64" CK, 40 BWPH, TRACE SAND, LIGHT GAS TTL BBLS RECOVERED: 3705 BBLS LEFT TO RECOVER: 7562
11:00	-			PROD			WELL TURNED TO SALES @ 1100 HR ON 1/09/2009 - FTP 1222#, CP 1222#, CK 20/64", 1100 MCFD, 1080 BWPD
1/10/2009	SUPERVISOR: WENDALL MYRICK						MD:
7:00	-	33					7 AM FLBK REPORT: CP 1925#, TP 1200#, 20/64" CK, 25 BWPH, trace SAND, 1200 GAS TTL BBLS RECOVERED: 4434 BBLS LEFT TO RECOVER: 6833
1/11/2009	SUPERVISOR: WENDALL MYRICK						MD:
7:00	-	33	A				7 AM FLBK REPORT: CP 1875#, TP 1250#, 20/64" CK, 18 BWPH, TRACE SAND, 1400 GAS TTL BBLS RECOVERED: 4912 BBLS LEFT TO RECOVER: 6355



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☒  
(highlight changes)

FORM 8

**WELL COMPLETION OR RECOMPLETION REPORT AND LOG**

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: <b>ML-22792</b>
b. TYPE OF WORK:		NEW WELL <input type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	6. IF INDIAN, ALLOTTEE OR TRIBE NAME
			DIFF. RESVR <input checked="" type="checkbox"/>	OTHER <b>RECOMPLETION</b>		7. UNIT or CA AGREEMENT NAME <b>UNIT #891008900A</b>
2. NAME OF OPERATOR: <b>KERR McGEE OIL &amp; GAS ONSHORE LP</b>						8. WELL NAME and NUMBER <b>NBU 1021-19E</b>
3. ADDRESS OF OPERATOR: <b>1368 S 1200 E</b> CITY <b>VERNAL</b> STATE <b>UT</b> ZIP <b>84078</b>					PHONE NUMBER: <b>(435) 781-7024</b>	9. API NUMBER: <b>4304739006</b>
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: <b>2146'FNL, 879'FWL LOT 2</b>						10. FIELD AND POOL, OR WILDCAT <b>NATURAL BUTTES</b>
AT TOP PRODUCING INTERVAL REPORTED BELOW:						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>SWNW 19 10S 21E</b>
AT TOTAL DEPTH:						12. COUNTY <b>UINTAH</b>
						13. STATE <b>UTAH</b>

14. DATE SPURRED: <b>6/22/2008</b>	15. DATE T.D. REACHED: <b>8/5/2008</b>	16. DATE COMPLETED: <b>1/9/2009</b>	ABANDONED <input type="checkbox"/>	READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): <b>5192'GL</b>
18. TOTAL DEPTH: MD <b>9,680</b> TVD	19. PLUG BACK T.D.: MD <b>9,619</b> TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD	
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)  <b>N/A</b>				23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
12 1/4"	9 5/8 J-55	36#		2,060		550			
7 7/8"	4 1/2 I-80	11.6#		9,680		2240			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	7,419							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) WASATCH	5,516	7,384			5,516 7,384	0.36	289	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) MESAVERDE	7,468	7,756			7,468 7,756	0.36	84	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
5516'-7384'	PMP 6992 BBLS SLICK H2O & 270,510# 30/50 OTTOWA SD
7468'-7756'	PMP 4275 BBLS SLICK H2O & 169,399# 30/50 OTTOWA SD

29. ENCLOSED ATTACHMENTS:

- |   |  |                                       |   |
|---|--|---------------------------------------|---|
| <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS                         | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT   | <input type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS   | <input type="checkbox"/> OTHER: _____ |   |

30. WELL STATUS:

**RECEIVED**  
**PROD**  
**FEB 09 2009**



## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 1/9/2009		TEST DATE: 1/23/2009		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,232		WATER – BBL: 240		PROD. METHOD: FLOWING							
CHOKE SIZE: 18/64		TBG. PRESS. 766		CSG. PRESS. 1,402		API GRAVITY		BTU – GAS		GAS/OIL RATIO		24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,232		WATER – BBL: 240		INTERVAL STATUS: PROD	

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED: 1/9/2009		TEST DATE: 1/23/2009		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,232		WATER – BBL: 240		PROD. METHOD: FLOWING							
CHOKE SIZE: 18/64		TBG. PRESS. 766		CSG. PRESS. 1,402		API GRAVITY		BTU – GAS		GAS/OIL RATIO		24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,232		WATER – BBL: 240		INTERVAL STATUS: PROD	

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL D (As shown in item #26)

INTERVAL D (AS SHOWN IN RUN #12)										
DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
GREEN RIVER MAHOGANY WASATCH MESAVERDE	1,113 1,831 4,415 7,456	7,013 9,570			

## 35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 2/6/2009

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top— Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-22792
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 1021-19E
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2146 FNL 0879 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNW Section: 19 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047390060000
<b>PHONE NUMBER:</b> 720 929-6507		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION	<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <div style="border: 1px solid black; padding: 2px; display: inline-block;">2/3/2016</div> <input type="checkbox"/> SPUD REPORT Date of Spud:
<input type="checkbox"/> DRILLING REPORT Report Date:	<input checked="" type="checkbox"/> OTHER			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

A WORKOVER/WELLBORE CLEANOUT HAS BEEN COMPLETED ON THE  
NBU 1021-19E WELL. PLEASE SEE THE ATTACHED OPERATIONS  
SUMMARY REPORT FOR DETAILS.

**Accepted by the  
Utah Division of  
Oil, Gas and Mining**

**FOR RECORD ONLY**

February 09, 2016

<b>NAME (PLEASE PRINT)</b> Kristina Geno	<b>PHONE NUMBER</b> 720 929-6824	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 2/8/2016	

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 1021-19E				Spud Conductor: 6/22/2008				Spud date: 6/23/2008			
Project: UTAH-UINTAH				Site: NBU 1021-19E				Rig name no.: GWS 1/1			
Event: WELL WORK EXPENSE				Start date: 1/26/2016				End date: 2/3/2016			
Active datum: RKB @5,208.00usft (above Mean Sea Level)				UWI: 0/10/S/21/E/19/0/SWNW/6/PM/N/2,146.00/E/0/0/0/0							
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation			
1/26/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM.			
	7:00 - 11:00	4.00	MAINT	30	H	P		RD RIG & ROAD RIG F/ STATE 1021-32H. MIRU RIG & SPOT RIG EQUIP.			
	11:00 - 17:00	6.00	MAINT	31	I	P		FWP = 40 PSI. BLW WELL DWN. ND WH. NU BOP. RU RIG FLOOR & TBG EQUIP. UNLAND TBG & LD 4 1/16 FMC TBG HNGR. PU RIH W/ 36 JTS 2 3/8 P-110 TBG & TAG @ 8895'. XO POOH LD 36 JTS. RU PIPE WRANGLE & RACKS. SWIFN.			
1/27/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM.			
	7:00 - 13:30	6.50	MAINT	45	A	P		SICP = 375 PSI. BLW WELL DWN. PUMP 20 BBLS DWN TBG. MIRU SCAN TECH. POOH SCAN TOTAL OF 246 JTS 2 3/8 L-80 TBG. FOUND 83 YB, 54 BB, 10 DBB & 99 RB. PITTING ON PIN ENDS 11,12,33,75,79,83-85,87-95,101-107,111-114, 116,126,129,135,220. LIGHT ID SCALE ON JT 215, HEAVY OD SCALE JTS 243-246. 24 PERF HOLES IN JT 246. RDMO SCAN TECH.			
	13:30 - 17:00	3.50	MAINT					PU 3 7/8 MILL, POBS, 1.875 XN. RIH W/ 138 JTS 2 3/8 L-80 YB, 6' P-110 PUP JT & 20 NEW 2 3/8 P-110 TBG. EOT @ 5000'. SWIFN. WINTERIZE WH & RIG EQUIP.			
1/28/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM.			
	7:00 - 10:00	3.00	MAINT	31	I	P		SICP = 350 PSI. BLW WELL DWN. PUMP 20 BBLS DWN TBG. CONT RIH F/ 5000'. TAG SCALE W/ 257 JTS @ 8135'.			
	10:00 - 17:30	7.50	MAINT	44	D	P		RU DRL EQUIP & WTF FU. BRK CONV CIRC 1hr 45 min T/ GET RETURNS. BEG MILLING F/ 8135' T/ 8389', FELL FREE. CIRC WELL CLEAN. STD BK DRL EQUIP. POOH LD 15 JTS. REMOVE DART VALVE. SWIFWE. WINTERIZE WH & RIG EQUIP.			
2/1/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM.			
	7:00 - 9:00	2.00	MAINT	31	I	P		SICP = 350 PSI. BLW WELL DWN. WAIT FOR WATER FOR 30 MIN, SNOWY ROADS. PUMP 20 DWN TBG. CONT RIH TAG SCALE @ 8833'.			
	9:00 - 14:30	5.50	MAINT	44	D	P		RU DRL EQUIP. BRK CONV CIRC W/ FU. 1hr 30 min T/ GET RETURNS. MILL DWN T/ 8960'. STOP MAKING HOLE. (OLD PUMP OFF BIT SUB) CIRC WELL CLEAN W/ FU. STD BCK DRL EQUIP.			

## US ROCKIES REGION

## Operation Summary Report

Well: NBU 1021-19E		Spud Conductor: 6/22/2008		Spud date: 6/23/2008	
Project: UTAH-UINTAH		Site: NBU 1021-19E			Rig name no.: GWS 1/1
Event: WELL WORK EXPENSE		Start date: 1/26/2016		End date: 2/3/2016	
Active datum: RKB @5,208.00usft (above Mean Sea Level)		UWI: 0/10/S/21/E/19/0/SWNW/6/PM/N/2,146.00/E/0/0/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	14:00 - 17:30	3.50	MAINT	31	I	P		POOH STD BCK 283 JTS 2 3/8 TBG. LD XN, POBS & 3 7/8 MILL. FOUND POBS BALL IN THE MIDDLE PORT IN MILL. PU 3 7/8 WO SHOE, 2' WO EXT, XO. RIH W/ 120 JTS SWIFN. EOT @ 3798'. WINTERIZE WH & RIG EQUIP.
2/2/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM
	7:00 - 9:00	2.00	MAINT	31	I	P		SICP = 490 PSI. BLW WELL DWN. PUMP 20 BBLS DWN. CONT RIH W/ WO SHOE & TBG. TAG OLD POBS @ 8962'.
	9:00 - 15:00	6.00	MAINT	44	D	P		RU DRL EQUIP. BRK CONV CIRC W/ FU ( 1hr 30min). WO OLD POBS @ 8962' & MILL DWN T/ 9373' =111' PAST BTM PERF @ 9262'. KICK IN N2 UNIT W/ FOAM UNIT & CIRC WELL CLEAN. RD DRL EQUIP.
	15:00 - 17:30	2.50	MAINT	31	I	P		POOH LD 50 JTS EXESS JTS 2 3/8 P-110 TBG. STD BCK 100 JTS. EOT @ 4620'. SWIFN. WINTERIZE WH & RIG EQUIP.
2/3/2016	6:45 - 7:00	0.25	MAINT	48		P		HSM
	7:00 - 9:00	2.00	MAINT	31	I	P		SICP = 598 PSI. BLW WELL DWN. PUMP 20 BBLS DWN TBG. FINISH POOH W/ TBG & LD WO SHOE W/ 2' EXT. FOUND OLD POBS INSIDE WO SHOE.
	9:00 - 13:00	4.00	MAINT	31	I	P		PU 1.875 XN/NC. RIH W/ 246 JTS 2 3/8 TBG. RU BROACH EQUIP. BROACH TBG. POOH W/ BROACH. RD BROACH EQUIP. PU 4 1/16 TBG HNG. LAND TBG W/ 4 1/16 TBG HNGR, 110 JTS 2 3/8 P-110, 6' P-110 PUP, 136 JTS 2 3/8 L-80 W/ 1.875 XN/NC. EOT @ 7802'. LOAD LEFT T/ RECOVER = 100 BBLS.
	13:00 - 18:00	5.00	MAINT	30	H			RD TBG EQUIP & RIG FLOOR. ND BOP, NU WH. SWI FOR PSI BUILD UP. RD RIG & RACK OUT RIG EQUIP. ROAD RIG T/ MS 3-34 SPOT RIG. SDFN.